

Results of Water Quality Testing
for
Maple Elementary School

Updated March 13, 2009

General Information:

Plumbing piping materials: mainly copper

Remediation plan:

This remediation plan is based on a Water Quality policy approved by the School Board. The policy includes standards for the presence of lead, cadmium, copper, iron and other substances in drinking water.

Status:

Policy Criteria:

The school has five sources that do not meet the policy criteria. Signs will be posted at:

03	S	audio visual
19	S	Family Support Workroom
27	S	Childcare medium sink
45	S	Pod C, Teacher's prep. Room
46	S	POD B, teacher's prep room

Follow-up monitoring: Will be performed in 2012.

Service: The school will be flushed after any breaks longer than five days.

Water Quality Testing Results:

Legend	
Symbol	Definition
SE	service entry (main)
B	bubbler
S	sink (faucet)
B/S	sink/bubbler combination
S/B	sink/bubbler combination
ppb	parts per billion
ppm	parts per million
NA	not applicable
None	no action required
Unk	unknown status or action
Sample	sample needs to be taken
Re-test	fixture needs to be resampled
Conf	resample to confirm measurement
No flush	not flushed before sampling
Sink	sampled faucet of S/B combo
Used	recently used; no 1st draw sample possible
PS	post sign
Disable(d)	fixture disabled in response to water quality testing
IF	install filter
RB	replace bubbler
RB/IF	replace bubbler and/or install filter
RF	replace faucet
RF/IF	replace faucet and/or install filter
BW	disable fixture and provide bottled water until remediated
Leaks	leaking fixture
NW	not working properly (sample S when B of S/B NW)
OS	out of service - disabled until fixed
RS	return to service - now passes testing
Rem	Removed from system - no longer exists

Table 1. Summary of Results

FIXTURE INFORMATION			LEAD		CADMIUM		COPPER		IRON		OK?
Fixture ID	Type	Location	Pass/Fail	Status	Pass/Fail	Status	Pass/Fail	Status	Pass/Fail	Status	Yes/No/Status
01	B	hallway	P	None	P	None	P	None	P	None	Yes
02	S/B	Pod A, Room A2	P	None	P	None	P	None	P	None	Yes
03	S	audio visual	F	PS	P	None	P	None	P	None	PS
04	S/B	room # B2	P	None	P	None	P	None	P	None	Yes
05	S/B	between B & C	P	None	P	None	P	None	P	None	Yes
05A	S	between B&C, by 5, right	P	None	P	None	P	None			Yes
06	S/B	between B & C	P	None	P	None	P	None	P	None	Yes
06A	S	between B&C, by 6, left	P	None	P	None	P	None			Yes
07	S/B	room # C2	P	None	P	None	P	None	P	None	Yes
08	S/B	room # E2 (now Pod F)	P	None	P	None	P	None	P	None	Yes
09	S/B	between D & E	P	None	P	None	P	None	P	None	Yes
09A	S	between D&E, by 9, left	P	None	P	None	P	None	P	None	Yes
10	S/B	between D & E	P	None	P	None	P	None	P	None	Yes
10A	S	between D&E, by 10, left	P	None	P	None	P	None			Yes
11	S/B	room # D2 (now Pod E)	P	None	P	None	P	None	P	None	Yes
18	S	nurses office	P	None	P	None	P	None	P	None	Yes
19	S	Family Support Workroom	F	PS	P	None	P	None	P	None	PS
20	S/B	hallway POD A; A-1	P	None	P	None	P	None	P	None	Yes
20A	S	hallway POD A, left	P	None	P	None	P	None			Yes
21	S	Workroom - staff next to principal	P	None	P	None	P	None	P	None	Yes
23	S	Kitchen, left sink	P	None	P	None	P	None	P	None	Yes
23A	S	kitchen	P	None	P	None	P	None			Yes
24	S	Kitchen	P	None	P	None	P	None	P	None	Yes
25	S	Faculty lounge	P	None	P	None	P	None	P	None	Yes
26	S	Childcare kitchen sink	P	None	P	None	P	None	P	None	Yes
27	S	Childcare medium sink	F	PS	P	None	P	None	P	None	PS
28	B	Childcare	P	None	P	None	P	None	P	None	Yes
30	S	Art room 150 W	P	None	P	None	P	None	P	None	Yes
31	S	Art room 150 E	P	None	P	None	P	None	P	None	Yes
32	B/S	Music/Platform 154	P	None	P	None	P	None	P	None	Yes
33	B/S	EBD 140	P	None	P	None	P	None	P	None	Yes
34	B/S	Resource 142	P	None	P	None	P	None	P	None	Yes
35	B/S	ELL 144	P	None	P	None	P	None	P	None	Yes
36	S	Pod A Teachers room	P	None	P	None	P	None	P	None	Yes
37	B	Hall 128 W	P	None	P	None	P	None	P	None	Yes
38	B	Hall 128 E	P	None	P	None	P	None	P	None	Yes
42	S/B	Pod A, Rm A3	P	None	P	None	P	None	P	None	Yes
43	B/S	Pod A, Room A1	P	None	P	None	P	None	P	None	Yes
44	S	Staff room between Pod E and Pod F	P	None	P	None	P	None	P	None	Yes
45	S	Pod C, Teacher's prep. Room	F	PS	P	None	P	None			PS
46	S	POD B, teacher's prep room	F	PS	P	None	P	None			PS
47	S	childcare kitchen	P	None	P	None	P	None			Yes
48	S	childcare midium, left to 27	P	None	P	None	P	None			Yes
49	S	kitchen handwash	P	None	P	None	P	None			Yes
50	S	kitchen handwash	P	None	P	None	P	None			Yes
51	B	POD D, outside girls bathroom, left	P	None	P	None	P	None	P	None	Yes
52	B	Pod D, outside boys bathroom, right	P	None	P	None	P	None			Yes

Table 2. Lead Test Results

FIXTURE INFORMATION			Initial Sampling				Follow-up Sampling 1				Follow-up Sampling 2				Follow-up Sampling 3				Follow-up Sampling 4			
Fixture ID	Type	Location	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail
01	B	hallway	4/9/2004	18	3										1/12/2005	4	4	P				
02	S/B	Pod A, Room A2					6/28/2004	26														
03	S	audio visual					6/28/2004	18														
04	S/B	room # B2	4/9/2004	17	3																	
05	S/B	between B & C	4/9/2004	230	3		6/28/2004	17	4						1/12/2005	3	<1	P				
05A	S	between B&C, by 5, right																				
06	S/B	between B & C	4/9/2004	52	2		6/28/2004	16	17						1/12/2005	<1	4	P				
06A	S	between B&C, by 6, left																				
07	S/B	room # C2																				
08	S/B	room # E2 (now Pod F)					6/28/2004	20														
09	S/B	between D & E	4/9/2004	10	<1	P	6/28/2004	15	5						1/12/2005	13	1		3/6/2005	<1	<1	P
09A	S	between D&E, by 9, left																				
10	S/B	between D & E	4/9/2004	470	2						11/5/2004	4	1	P	1/12/2005	3	<1	P				
10A	S	between D&E, by 10, left																				
11	S/B	room # D2 (now Pod E)					6/28/2004	16														
18	S	nurses office	4/9/2004	16	1																	
19	S	Family Support Workroom	4/9/2004	10	1	P																
20	S/B	hallway POD A; A-1	4/9/2004	33	7		6/28/2004	13	6						1/12/2005	3	<1	P				
20A	S	hallway POD A, left																				
21	S	Workroom - staff next to principal																				
23	S	Kitchen, left sink																				
23A	S	kitchen																				
24	S	Kitchen																				
25	S	Faculty lounge																				
26	S	Childcare kitchen sink																				
27	S	Childcare medium sink																				
28	B	Childcare																				
30	S	Art room 150 W																				
31	S	Art room 150 E																				
32	B/S	Music/Platform 154																				
33	B/S	EBD 140																				
34	B/S	Resource 142																				
35	B/S	ELL 144																				
36	S	Pod A Teachers room																				
37	B	Hall 128 W																				
38	B	Hall 128 E																				
42	S/B	Pod A, Rm A3																				
43	B/S	Pod A, Room A1																				
44	S	Staff room between Pod E and Pod F																				
45	S	Pod C, Teacher's prep. Room																				
46	S	POD B, teacher's prep room																				
47	S	childcare kitchen																				
48	S	childcare midium, left to 27																				
49	S	kitchen handwash																				
50	S	kitchen handwash																				
51	B	POD D, outside girls bathroom, left																				
52	B	Pod D, outside boys bathroom, right																				

Table 2. Lead Test Results (Continued)

FIXTURE INFORMATION			Follow-up Sampling 5				Follow-up Sampling 6				Follow-up Sampling 7				Follow-up Sampling 8				Follow-up Sampling 9				
Fixture ID	Type	Location	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	
01	B	hallway	5/18/2006	<1	<1	P																	
02	S/B	Pod A, Room A2	5/18/2006	6	<1	P					9/29/2006	21	1		12/21/2006	30	<1		3/21/2007	8	<1	P	
03	S	audio visual	5/18/2006	22	1						9/29/2006	16	2		12/21/2006	21	3		3/21/2007	13	<1		
04	S/B	room # B2	5/18/2006	2	<1	P																	
05	S/B	between B & C	5/18/2006	2	<1	P									12/21/2006	1	<1	P					
05A	S	between B&C, by 5, right																					
06	S/B	between B & C	5/18/2006	2	<1	P																	
06A	S	between B&C, by 6, left																					
07	S/B	room # C2	5/18/2006	24	3						9/29/2006	18	3		12/21/2006	21	2		3/21/2007	8	6	P	
08	S/B	room # E2 (now Pod F)	5/18/2006	12	1						9/29/2006	9	1	P									
09	S/B	between D & E	5/18/2006	2	1	P																	
09A	S	between D&E, by 9, left																					
10	S/B	between D & E	5/18/2006	<1	<1	P																	
10A	S	between D&E, by 10, left																					
11	S/B	room # D2 (now Pod E)	5/18/2006	12	2						9/29/2006	9	1	P									
18	S	nurses office	5/18/2006	21	1						9/29/2006	11	2		12/21/2006	34	2		3/21/2007	14	<1		
19	S	Family Support Workroom	5/18/2006	22	1		8/30/2006	44	2		9/29/2006	21	1		12/21/2006	32	<1		3/21/2007	11	<1		
20	S/B	hallway POD A; A-1	5/18/2006	4	<1	P	8/30/2006	2	<1	P													
20A	S	hallway POD A, left																					
21	S	Workroom - staff next to principal	5/18/2006	18	1		8/30/2006	9	2	P													
23	S	Kitchen, left sink	5/18/2006	120	4		8/30/2006	96	4		9/29/2006	70	3		12/21/2006	95	1		3/21/2007	14	<1		
23A	S	kitchen																					
24	S	Kitchen	5/18/2006	15	1		8/30/2006	18	2		9/29/2006	8	<1	P									
25	S	Faculty lounge	5/18/2006	8	2	P	8/30/2006	8	1	P													
26	S	Childcare kitchen sink	5/18/2006	12	1		8/30/2006	5	2	P													
27	S	Childcare medium sink	5/18/2006	16	2		8/30/2006	9	2	P													
28	B	Childcare	5/18/2006	4	2	P	8/30/2006	1	<1	P					12/21/2006	3	<1	P					
30	S	Art room 150 W	5/18/2006	17	2		8/30/2006	6	<1	P													
31	S	Art room 150 E	5/18/2006	14	2		8/30/2006	7	<1	P													
32	B/S	Music/Platform 154	5/18/2006	8	2	P	8/30/2006	8	1	P													
33	B/S	EBD 140	5/18/2006	7	2	P	8/30/2006	10	2	P													
34	B/S	Resource 142	5/18/2006	4	2	P	8/30/2006	7	5	P													
35	B/S	ELL 144	5/18/2006	3	3	P	8/30/2006	8	3	P													
36	S	Pod A Teachers room	5/18/2006	27	3		8/30/2006	22	4		9/29/2006	26	1		12/21/2006	23	1		3/21/2007	14	<1		
37	B	Hall 128 W	5/18/2006	11	2		8/30/2006	7	<1	P													
38	B	Hall 128 E	5/18/2006	19	2		8/30/2006	10	<1	P													
42	S/B	Pod A, Rm A3									9/29/2006	22	2		12/21/2006	27	3		3/21/2007	9	<1	P	
43	B/S	Pod A, Room A1									9/29/2006	3	2	P	12/21/2006	3	<1	P					
44	S	Staff room between Pod E and Pod F													12/21/2006	7	1	P					
45	S	Pod C, Teacher's prep. Room																					
46	S	POD B, teacher's prep room																					
47	S	childcare kitchen																					
48	S	childcare midium, left to 27																					
49	S	kitchen handwash																					
50	S	kitchen handwash																					
51	B	POD D, outside girls bathroom, left																					
52	B	Pod D, outside boys bathroom, right																					

Table 2. Lead Test Results (Continued-2)

FIXTURE INFORMATION			Follow-up Sampling 10				Follow-up Sampling 11				Follow-up Sampling 12				Follow-up Sampling 13				Summary Status	
Fixture ID	Type	Location	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Pass/Fail	Status
01	B	hallway													2/19/2009	1	2	P	P	None
02	S/B	Pod A, Room A2					9/13/2007	6	1	P					2/19/2009	4	<1	P	P	None
03	S	audio visual					9/13/2007	9	1	P					2/19/2009	12	1		F	PS
04	S/B	room # B2									10/2/2007	<1	<1	P	2/19/2009	5	1	P	P	None
05	S/B	between B & C													2/19/2009	<1	<1	P	P	None
05A	S	between B&C, by 5, right					9/13/2007	3	<1	P					2/19/2009	<1	1	P	P	None
06	S/B	between B & C													2/19/2009	<1	<1	P	P	None
06A	S	between B&C, by 6, left					9/13/2007	3	<1	P					2/19/2009	1	<1	P	P	None
07	S/B	room # C2					9/13/2007	9	2	P					2/19/2009	4	1	P	P	None
08	S/B	room # E2 (now Pod F)					9/13/2007	5	<1	P					2/19/2009	3	1	P	P	None
09	S/B	between D & E													2/19/2009	<1	<1	P	P	None
09A	S	between D&E, by 9, left					9/13/2007	12	<1						2/19/2009	3	<1	P	P	None
10	S/B	between D & E													2/19/2009	1	<1	P	P	None
10A	S	between D&E, by 10, left					9/13/2007	<1	<1	P					2/19/2009	1	<1	P	P	None
11	S/B	room # D2 (now Pod E)					9/13/2007	4	<1	P					2/19/2009	3	1	P	P	None
18	S	nurses office	7/20/2007	17	2		9/13/2007	13	<1						2/19/2009	2	<1	P	P	None
19	S	Family Support Workroom					9/13/2007	15	<1						2/19/2009	12	1		F	PS
20	S/B	hallway POD A; A-1													2/19/2009	<1	<1	P	P	None
20A	S	hallway POD A, left					9/13/2007	3	2	P					2/19/2009	1	3	P	P	None
21	S	Workroom - staff next to principal													2/19/2009	8	<1	P	P	None
23	S	Kitchen, left sink					9/13/2007	18	2						2/19/2009	<1	<1	P	P	None
23A	S	kitchen					9/13/2007	4	2	P					2/19/2009	<1	3	P	P	None
24	S	Kitchen													2/19/2009	3	<1	P	P	None
25	S	Faculty lounge													2/19/2009	2	<1	P	P	None
26	S	Childcare kitchen sink													2/19/2009	<1	<1	P	P	None
27	S	Childcare medium sink													2/19/2009	12	<1		F	PS
28	B	Childcare													2/19/2009	<1	<1	P	P	None
30	S	Art room 150 W													2/19/2009	1	<1	P	P	None
31	S	Art room 150 E													2/19/2009	2	<1	P	P	None
32	B/S	Music/Platform 154													2/19/2009	1	<1	P	P	None
33	B/S	EBD 140													2/19/2009	1	<1	P	P	None
34	B/S	Resource 142													2/19/2009	<1	<1	P	P	None
35	B/S	ELL 144													2/19/2009	1	<1	P	P	None
36	S	Pod A Teachers room					9/13/2007	18	<1						2/19/2009	10	<1	P	P	None
37	B	Hall 128 W													2/19/2009	<1	<1	P	P	None
38	B	Hall 128 E													2/19/2009	<1	<1	P	P	None
42	S/B	Pod A, Rm A3					9/13/2007	8	<1	P					2/19/2009	5	<1	P	P	None
43	B/S	Pod A, Room A1													2/19/2009	1	<1	P	P	None
44	S	Staff room between Pod E and Pod F													2/19/2009	6	<1	P	P	None
45	S	Pod C, Teacher's prep. Room					9/13/2007	27	3						2/19/2009	20	2		F	PS
46	S	POD B, teacher's prep room					9/13/2007	21	1						2/19/2009	14	<1		F	PS
47	S	childcare kitchen					9/13/2007	5	1	P					2/19/2009	<1	<1	P	P	None
48	S	childcare midium, left to 27					9/13/2007	10	1	P					2/19/2009	7	<1	P	P	None
49	S	kitchen handwash					9/13/2007	44	3						2/19/2009	4	<1	P	P	None
50	S	kitchen handwash					9/13/2007	11	2						2/19/2009	4	4	P	P	None
51	B	POD D, outside girls bathroom, left					9/13/2007	5	4	P					2/19/2009	1	<1	P	P	None
52	B	Pod D, outside boys bathroom, right					9/13/2007	2	<1	P					2/19/2009	<1	1	P	P	None

Table 3. Cadmium Test Results

FIXTURE INFORMATION			Initial Sampling				Follow-up Sampling 1				Follow-up Sampling 2				Follow-up Sampling 3				Follow-up Sampling 4				Follow-up Sampling 5			
Fixture ID	Type	Location	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail
01	B	hallway	4/9/04	<1	<1	P					1/12/05	<1	<1	P	5/18/06	<1	<1	P								
02	S/B	Pod A, Room A2													5/18/06	<1	<1	P					9/29/06	<1	<1	P
03	S	audio visual													5/18/06	<1	<1	P								
04	S/B	room # B2	4/9/04	<1	<1	P									5/18/06	<1	<1	P								
05	S/B	between B & C	4/9/04	<1	<1	P					1/12/05	<1	<1	P	5/18/06	<1	<1	P								
05A	S	between B&C, by 5, right																								
06	S/B	between B & C	4/9/04	<1	<1	P					1/12/05	<1	<1	P	5/18/06	<1	<1	P								
06A	S	between B&C, by 6, left																								
07	S/B	room # C2													5/18/06	<1	<1	P								
08	S/B	room # E2 (now Pod F)													5/18/06	<1	<1	P								
09	S/B	between D & E	4/9/04	<1	<1	P					1/12/05	<1	<1	P	5/18/06	<1	<1	P								
09A	S	between D&E, by 9, left																								
10	S/B	between D & E	4/9/04	<1	<1	P	11/5/04	<1	<1	P	1/12/05	<1	<1	P	5/18/06	<1	<1	P								
10A	S	between D&E, by 10, left																								
11	S/B	room # D2 (now Pod E)													5/18/06	<1	<1	P								
18	S	nurses office	4/9/04	<1	<1	P									5/18/06	<1	<1	P								
19	S	Family Support Workroom	4/9/04	<1	<1	P									5/18/06	<1	<1	P	8/30/06	<1	<1	P				
20	S/B	hallway POD A; A-1	4/9/04	<1	<1	P					1/12/05	<1	<1	P	5/18/06	<1	<1	P	8/30/06	<1	<1	P				
20A	S	hallway POD A, left																								
21	S	Workroom - staff next to principal													5/18/06	<1	<1	P	8/30/06	<1	<1	P				
23	S	Kitchen, left sink													5/18/06	<1	<1	P	8/30/06	<1	<1	P				
23A	S	kitchen																								
24	S	Kitchen													5/18/06	<1	<1	P	8/30/06	<1	<1	P				
25	S	Faculty lounge													5/18/06	<1	<1	P	8/30/06	<1	<1	P				
26	S	Childcare kitchen sink													5/18/06	<1	<1	P	8/30/06	<1	<1	P				
27	S	Childcare medium sink													5/18/06	<1	<1	P	8/30/06	<1	<1	P				
28	B	Childcare													5/18/06	<1	<1	P	8/30/06	<1	<1	P				
30	S	Art room 150 W													5/18/06	<1	<1	P	8/30/06	<1	<1	P				
31	S	Art room 150 E													5/18/06	<1	<1	P	8/30/06	<1	<1	P				
32	B/S	Music/Platform 154													5/18/06	<1	<1	P	8/30/06	<1	<1	P				
33	B/S	EBD 140													5/18/06	<1	<1	P	8/30/06	<1	<1	P				
34	B/S	Resource 142													5/18/06	<1	<1	P	8/30/06	<1	<1	P				
35	B/S	ELL 144													5/18/06	<1	<1	P	8/30/06	<1	<1	P				
36	S	Pod A Teachers room													5/18/06	<1	<1	P	8/30/06	<1	<1	P				
37	B	Hall 128 W													5/18/06	<1	<1	P	8/30/06	<1	<1	P				
38	B	Hall 128 E													5/18/06	<1	<1	P	8/30/06	<1	<1	P				
42	S/B	Pod A, Rm A3																					9/29/06	<1	<1	P
43	B/S	Pod A, Room A1																					9/29/06	<1	<1	P
44	S	Staff room between Pod E and Pod F																								
45	S	Pod C, Teacher's prep. Room																								
46	S	POD B, teacher's prep room																								
47	S	childcare kitchen																								
48	S	childcare midium, left to 27																								
49	S	kitchen handwash																								
50	S	kitchen handwash																								
51	B	POD D, outside girls bathroom, left																								
52	B	Pod D, outside boys bathroom, right																								

Table 3. Cadmium Test Results (Continued)

FIXTURE INFORMATION			Follow-up Sampling 6				Follow-up Sampling 7				Follow-up Sampling 8				Follow-up Sampling 9				Follow-up Sampling 10				Summary Status	
Fixture ID	Type	Location	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass/ Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Pass/Fail	Status
01	B	hallway																	2/19/2009	<1	<1	P	P	None
02	S/B	Pod A, Room A2									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
03	S	audio visual									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
04	S/B	room # B2													10/2/2007	<1	<1	P	2/19/2009	<1	<1	P	P	None
05	S/B	between B & C																	2/19/2009	<1	<1	P	P	None
05A	S	between B&C, by 5, right									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
06	S/B	between B & C																	2/19/2009	<1	<1	P	P	None
06A	S	between B&C, by 6, left									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
07	S/B	room # C2									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
08	S/B	room # E2 (now Pod F)									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
09	S/B	between D & E																	2/19/2009	<1	<1	P	P	None
09A	S	between D&E, by 9, left									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
10	S/B	between D & E																	2/19/2009	<1	<1	P	P	None
10A	S	between D&E, by 10, left									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
11	S/B	room # D2 (now Pod E)									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
18	S	nurses office					7/20/2007	<1	<1	P	9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
19	S	Family Support Workroom									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
20	S/B	hallway POD A; A-1																	2/19/2009	<1	<1	P	P	None
20A	S	hallway POD A, left									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
21	S	Workroom - staff next to principal																	2/19/2009	<1	<1	P	P	None
23	S	Kitchen, left sink									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
23A	S	kitchen									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
24	S	Kitchen																	2/19/2009	<1	<1	P	P	None
25	S	Faculty lounge																	2/19/2009	<1	<1	P	P	None
26	S	Childcare kitchen sink																	2/19/2009	<1	<1	P	P	None
27	S	Childcare medium sink																	2/19/2009	<1	<1	P	P	None
28	B	Childcare																	2/19/2009	<1	<1	P	P	None
30	S	Art room 150 W																	2/19/2009	<1	<1	P	P	None
31	S	Art room 150 E																	2/19/2009	<1	<1	P	P	None
32	B/S	Music/Platform 154																	2/19/2009	<1	<1	P	P	None
33	B/S	EBD 140																	2/19/2009	<1	<1	P	P	None
34	B/S	Resource 142																	2/19/2009	<1	<1	P	P	None
35	B/S	ELL 144																	2/19/2009	<1	<1	P	P	None
36	S	Pod A Teachers room									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
37	B	Hall 128 W																	2/19/2009	<1	<1	P	P	None
38	B	Hall 128 E																	2/19/2009	<1	<1	P	P	None
42	S/B	Pod A, Rm A3									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
43	B/S	Pod A, Room A1																	2/19/2009	<1	<1	P	P	None
44	S	Staff room between Pod E and Pod F	12/21/2006	<1	<1	P													2/19/2009	<1	<1	P	P	None
45	S	Pod C, Teacher's prep. Room									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
46	S	POD B, teacher's prep room									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
47	S	childcare kitchen									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
48	S	childcare midium, left to 27									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
49	S	kitchen handwash									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
50	S	kitchen handwash									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
51	B	POD D, outside girls bathroom, left									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None
52	B	Pod D, outside boys bathroom, right									9/13/2007	<1	<1	P					2/19/2009	<1	<1	P	P	None

Table 4. Copper Test Results

FIXTURE INFORMATION			Initial Sampling				Follow-up Sampling 1				Follow-up Sampling 2				Follow-up Sampling 3				Follow-up Sampling 4				
Fixture ID	Type	Location	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	
01	B	hallway					1/12/2005	0.011	0.034	P	5/18/2006	0.007	<0.002	P									
02	S/B	Pod A, Room A2									5/18/2006	0.31	0.017	P					9/29/2006	0.166	0.067	P	
03	S	audio visual									5/18/2006	0.31	0.1	P									
04	S/B	room # B2									5/18/2006	0.065	0.037	P									
05	S/B	between B & C	4/9/2004		0.12	P	1/12/2005	0.007	0.004	P	5/18/2006	0.056	0.009	P									
05A	S	between B&C, by 5, right																					
06	S/B	between B & C					1/12/2005	0.01	0.011	P	5/18/2006	0.019	0.003	P									
06A	S	between B&C, by 6, left																					
07	S/B	room # C2									5/18/2006	0.32	0.42	P									
08	S/B	room # E2 (now Pod F)									5/18/2006	0.37	0.14	P									
09	S/B	between D & E					1/12/2005	0.03	0.013	P	5/18/2006	0.037	0.011	P									
09A	S	between D&E, by 9, left																					
10	S/B	between D & E	4/9/2004	2			1/12/2005	0.01	0.012	P	5/18/2006	0.008	0.002	P									
10A	S	between D&E, by 10, left																					
11	S/B	room # D2 (now Pod E)									5/18/2006	0.45	0.42	P									
18	S	nurses office	4/9/2004	0.35		P					5/18/2006	0.33	0.16	P									
19	S	Family Support Workroom	4/9/2004	0.24		P					5/18/2006	0.21	0.079	P	8/30/2006	0.322	0.056	P					
20	S/B	hallway POD A; A-1					1/12/2005	0.009	0.007	P	5/18/2006	0.34	0.2	P	8/30/2006	0.043	0.093	P					
20A	S	hallway POD A, left																					
21	S	Workroom - staff next to principal									5/18/2006	0.24	0.15	P	8/30/2006	0.19	0.131	P					
23	S	Kitchen, left sink									5/18/2006	0.091	0.35	P	8/30/2006	0.056	0.263	P					
23A	S	kitchen																					
24	S	Kitchen									5/18/2006	0.16	0.24	P	8/30/2006	0.158	0.196	P					
25	S	Faculty lounge									5/18/2006	0.41	0.4	P	8/30/2006	0.217	0.262	P					
26	S	Childcare kitchen sink									5/18/2006	0.39	0.24	P	8/30/2006	0.279	0.185	P					
27	S	Childcare medium sink									5/18/2006	0.3	0.33	P	8/30/2006	0.197	0.238	P					
28	B	Childcare									5/18/2006	0.33	0.27	P	8/30/2006	0.232	0.232	P					
30	S	Art room 150 W									5/18/2006	0.4	0.2	P	8/30/2006	0.257	0.226	P					
31	S	Art room 150 E									5/18/2006	0.31	0.18	P	8/30/2006	0.2	0.222	P					
32	B/S	Music/Platform 154									5/18/2006	0.32	0.18	P	8/30/2006	0.289	0.219	P					
33	B/S	EBD 140									5/18/2006	0.52	0.47	P	8/30/2006	0.319	0.258	P					
34	B/S	Resource 142									5/18/2006	0.51	0.54	P	8/30/2006	0.28	0.334	P					
35	B/S	ELL 144									5/18/2006	0.33	0.34	P	8/30/2006	0.261	0.25	P					
36	S	Pod A Teachers room									5/18/2006	0.18	0.072	P	8/30/2006	0.242	0.343	P					
37	B	Hall 128 W									5/18/2006	0.54	0.62	P	8/30/2006	0.3	0.253	P					
38	B	Hall 128 E									5/18/2006	0.5	0.26	P	8/30/2006	0.425	0.455	P					
42	S/B	Pod A, Rm A3																	9/29/2006	0.164	0.293	P	
43	B/S	Pod A, Room A1																	9/29/2006	0.333	0.164	P	
44	S	Staff room between Pod E and Pod F																					
45	S	Pod C, Teacher's prep. Room																					
46	S	POD B, teacher's prep room																					
47	S	childcare kitchen																					
48	S	childcare midium, left to 27																					
49	S	kitchen handwash																					
50	S	kitchen handwash																					
51	B	POD D, outside girls bathroom, left																					
52	B	Pod D, outside boys bathroom, right																					

Table 4. Copper Test Results (Continued)

FIXTURE INFORMATION			Follow-up Sampling 5				Follow-up Sampling 6				Follow-up Sampling 7				Follow-up Sampling 8				Follow-up Sampling 9				Summary Status	
Fixture ID	Type	Location	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Pass/Fail	Status
01	B	hallway																	2/19/2009	0.004	0.02	P	P	None
02	S/B	Pod A, Room A2									9/13/2007	0.326	0.118	P					2/19/2009	0.167	0.057	P	P	None
03	S	audio visual									9/13/2007	0.312	0.278	P					2/19/2009	0.231	0.255	P	P	None
04	S/B	room # B2													10/2/2007	0.057	0.135	P	2/19/2009	0.183	0.164	P	P	None
05	S/B	between B & C																	2/19/2009	0.022	0.005	P	P	None
05A	S	between B&C, by 5, right									9/13/2007	0.192	0.064	P					2/19/2009	0.182	0.039	P	P	None
06	S/B	between B & C																	2/19/2009	0.007	0.012	P	P	None
06A	S	between B&C, by 6, left									9/13/2007	0.204	0.109	P					2/19/2009	0.186	0.051	P	P	None
07	S/B	room # C2									9/13/2007	0.407	0.434	P					2/19/2009	0.21	0.231	P	P	None
08	S/B	room # E2 (now Pod F)									9/13/2007	0.444	0.341	P					2/19/2009	0.208	0.163	P	P	None
09	S/B	between D & E																	2/19/2009	0.005	0.01	P	P	None
09A	S	between D&E, by 9, left									9/13/2007	0.228	0.139	P					2/19/2009	0.103	0.055	P	P	None
10	S/B	between D & E																	2/19/2009	0.281	0.075	P	P	None
10A	S	between D&E, by 10, left									9/13/2007	0.318	0.127	P					2/19/2009	0.018	0.012	P	P	None
11	S/B	room # D2 (now Pod E)									9/13/2007	0.51	0.421	P					2/19/2009	0.237	0.215	P	P	None
18	S	nurses office					7/20/2007	0.306	0.245	P	9/13/2007	0.328	0.11	P					2/19/2009	0.242	0.106	P	P	None
19	S	Family Support Workroom									9/13/2007	0.148	0.062	P					2/19/2009	0.128	0.034	P	P	None
20	S/B	hallway POD A; A-1																	2/19/2009	0.013	0.009	P	P	None
20A	S	hallway POD A, left									9/13/2007	0.188	0.122	P					2/19/2009	0.222	0.097	P	P	None
21	S	Workroom - staff next to principal																	2/19/2009	0.136	0.046	P	P	None
23	S	Kitchen, left sink									9/13/2007	0.191	0.088	P					2/19/2009	0.245	0.123	P	P	None
23A	S	kitchen									9/13/2007	0.257	0.101	P					2/19/2009	0.112	0.109	P	P	None
24	S	Kitchen																	2/19/2009	0.205	0.142	P	P	None
25	S	Faculty lounge																	2/19/2009	0.265	0.263	P	P	None
26	S	Childcare kitchen sink																	2/19/2009	0.199	0.146	P	P	None
27	S	Childcare medium sink																	2/19/2009	0.157	0.23	P	P	None
28	B	Childcare																	2/19/2009	0.233	0.167	P	P	None
30	S	Art room 150 W																	2/19/2009	0.21	0.17	P	P	None
31	S	Art room 150 E																	2/19/2009	0.279	0.189	P	P	None
32	B/S	Music/Platform 154																	2/19/2009	0.241	0.181	P	P	None
33	B/S	EBD 140																	2/19/2009	0.284	0.325	P	P	None
34	B/S	Resource 142																	2/19/2009	0.269	0.342	P	P	None
35	B/S	ELL 144																	2/19/2009	0.287	0.222	P	P	None
36	S	Pod A Teachers room									9/13/2007	0.198	0.117	P					2/19/2009	0.153	0.086	P	P	None
37	B	Hall 128 W																	2/19/2009	0.281	0.236	P	P	None
38	B	Hall 128 E																	2/19/2009	0.313	0.257	P	P	None
42	S/B	Pod A, Rm A3									9/13/2007	0.241	0.332	P					2/19/2009	0.132	0.186	P	P	None
43	B/S	Pod A, Room A1																	2/19/2009	0.171	0.08	P	P	None
44	S	Staff room between Pod E and Pod F	12/21/2006	0.339	0.174	P													2/19/2009	0.297	0.06	P	P	None
45	S	Pod C, Teacher's prep. Room									9/13/2007	0.18	0.167	P					2/19/2009	0.205	0.141	P	P	None
46	S	POD B, teacher's prep room									9/13/2007	0.252	0.123	P					2/19/2009	0.158	0.056	P	P	None
47	S	childcare kitchen									9/13/2007	0.256	0.21	P					2/19/2009	0.252	0.158	P	P	None
48	S	childcare midium, left to 27									9/13/2007	0.249	0.301	P					2/19/2009	0.221	0.169	P	P	None
49	S	kitchen handwash									9/13/2007	0.332	0.222	P					2/19/2009	0.226	0.164	P	P	None
50	S	kitchen handwash									9/13/2007	0.226	0.188	P					2/19/2009	0.23	0.209	P	P	None
51	B	POD D, outside girls bathroom, left									9/13/2007	0.074	0.12	P					2/19/2009	0.075	0.155	P	P	None
52	B	Pod D, outside boys bathroom, right									9/13/2007	0.114	0.158	P					2/19/2009	0.127	0.136	P	P	None

Table 5. Iron Test Results

FIXTURE INFORMATION			Initial Sampling				Follow-up Sampling 1				Follow-up Sampling 2			
Fixture ID	Type	Location	Sampled	1st Draw	Flush 2m	Pass/Fail	Sampled	1st Draw	Flush 2m	Pass/Fail	Sampled	1st Draw	Flush 2m	Pass/Fail
01	B	hallway					5/18/2006		<0.05	P				
02	S/B	Pod A, Room A2					5/18/2006		<0.05	P				
03	S	audio visual					5/18/2006		0.092	P				
04	S/B	room # B2					5/18/2006		0.084	P				
05	S/B	between B & C					5/18/2006		<0.05	P				
05A	S	between B&C, by 5, right												
06	S/B	between B & C					5/18/2006		<0.05	P				
06A	S	between B&C, by 6, left												
07	S/B	room # C2					5/18/2006		0.088	P				
08	S/B	room # E2 (now Pod F)					5/18/2006		0.082	P				
09	S/B	between D & E					5/18/2006		<0.05	P				
09A	S	between D&E, by 9, left												
10	S/B	between D & E	4/9/2004	0.22		P	5/18/2006		<0.05	P				
10A	S	between D&E, by 10, left												
11	S/B	room # D2 (now Pod E)					5/18/2006		0.091	P				
18	S	nurses office	4/9/2004	0.11		P	5/18/2006		0.078	P				
19	S	Family Support Workroom	4/9/2004	0.1		P	5/18/2006		0.075	P	8/30/2006		0.137	P
20	S/B	hallway POD A; A-1					5/18/2006		0.089	P	8/30/2006		0.115	P
20A	S	hallway POD A, left												
21	S	Workroom - staff next to principal					5/18/2006		0.081	P	8/30/2006		0.102	P
23	S	Kitchen, left sink					5/18/2006		0.078	P	8/30/2006		0.186	P
23A	S	kitchen												
24	S	Kitchen					5/18/2006		0.077	P	8/30/2006		0.239	P
25	S	Faculty lounge					5/18/2006		0.111	P	8/30/2006		0.12	P
26	S	Childcare kitchen sink					5/18/2006		0.119	P	8/30/2006		0.415	P
27	S	Childcare medium sink					5/18/2006		0.121	P	8/30/2006		0.328	P
28	B	Childcare					5/18/2006		0.098	P	8/30/2006		0.156	P
30	S	Art room 150 W					5/18/2006		0.113	P	8/30/2006		0.118	P
31	S	Art room 150 E					5/18/2006		0.093	P	8/30/2006		0.122	P
32	B/S	Music/Platform 154					5/18/2006		0.101	P	8/30/2006		0.12	P
33	B/S	EBD 140					5/18/2006		0.103	P	8/30/2006		0.169	P
34	B/S	Resource 142					5/18/2006		0.098	P	8/30/2006		0.111	P
35	B/S	ELL 144					5/18/2006		0.088	P	8/30/2006		0.124	P
36	S	Pod A Teachers room					5/18/2006		0.091	P	8/30/2006		0.153	P
37	B	Hall 128 W					5/18/2006		0.109	P	8/30/2006		0.108	P
38	B	Hall 128 E					5/18/2006		0.101	P	8/30/2006		0.106	P
42	S/B	Pod A, Rm A3												
43	B/S	Pod A, Room A1												
44	S	Staff room between Pod E and Pod F												
45	S	Pod C, Teacher's prep. Room												
46	S	POD B, teacher's prep room												
47	S	childcare kitchen												
48	S	childcare midium, left to 27												
49	S	kitchen handwash												
50	S	kitchen handwash												
51	B	POD D, outside girls bathroom, left												
52	B	Pod D, outside boys bathroom, right												

Table 5. Iron Test Results (continued)

FIXTURE INFORMATION			Follow-up Sampling 3				Follow-up Sampling 4				Follow-up Sampling 5				Summary Status	
Fixture ID	Type	Location	Sampled	1st Draw	Flush 2m	Pass/Fail	Sampled	1st Draw	Flush 2m	Pass/Fail	Sampled	1st Draw	Flush 2m	Pass/Fail	Pass/Fail	Status
01	B	hallway													P	None
02	S/B	Pod A, Room A2	9/29/2006		0.09	P									P	None
03	S	audio visual													P	None
04	S/B	room # B2									2/19/2009		0.085	P	P	None
05	S/B	between B & C													P	None
05A	S	between B&C, by 5, right														
06	S/B	between B & C													P	None
06A	S	between B&C, by 6, left														
07	S/B	room # C2													P	None
08	S/B	room # E2 (now Pod F)													P	None
09	S/B	between D & E													P	None
09A	S	between D&E, by 9, left									2/19/2009		0.103	P	P	None
10	S/B	between D & E													P	None
10A	S	between D&E, by 10, left														
11	S/B	room # D2 (now Pod E)													P	None
18	S	nurses office													P	None
19	S	Family Support Workroom													P	None
20	S/B	hallway POD A; A-1													P	None
20A	S	hallway POD A, left														
21	S	Workroom - staff next to principal													P	None
23	S	Kitchen, left sink													P	None
23A	S	kitchen														
24	S	Kitchen									2/19/2009		0.06	P	P	None
25	S	Faculty lounge									2/19/2009		0.061	P	P	None
26	S	Childcare kitchen sink													P	None
27	S	Childcare medium sink									2/19/2009		0.064	P	P	None
28	B	Childcare													P	None
30	S	Art room 150 W													P	None
31	S	Art room 150 E													P	None
32	B/S	Music/Platform 154													P	None
33	B/S	EBD 140													P	None
34	B/S	Resource 142													P	None
35	B/S	ELL 144													P	None
36	S	Pod A Teachers room													P	None
37	B	Hall 128 W													P	None
38	B	Hall 128 E													P	None
42	S/B	Pod A, Rm A3					12/21/2006		0.074	P					P	None
43	B/S	Pod A, Room A1					12/21/2006		0.164	P	2/19/2009		0.079	P	P	None
44	S	Staff room between Pod E and Pod F					12/21/2006		0.169	P					P	None
45	S	Pod C, Teacher's prep. Room														
46	S	POD B, teacher's prep room														
47	S	childcare kitchen														
48	S	childcare midium, left to 27														
49	S	kitchen handwash														
50	S	kitchen handwash														
51	B	POD D, outside girls bathroom, left									2/19/2009		0.136	P	P	None
52	B	Pod D, outside boys bathroom, right														

Table 6. Service Entry Test Results

Test Results (Service Entry/SE, Units as Shown)						
SOURCE INFORMATION			<i>Most Recent Sampling</i>			
Fixture ID	Type	Location	Item	Sampled	Max Value	Pass/Fail
00	SE	see map	Arsenic	19-Feb-09	2 ppb	P
00	SE	see map	Cadmium	19-Feb-09	1 ppb	P
00	SE	see map	Copper	19-Feb-09	0.007 ppm	P
00	SE	see map	Iron	19-Feb-09	0.163 ppm	P
00	SE	see map	Lead	19-Feb-09	1 ppb	P
00	SE	see map	Total Coliforms	19-Feb-09	<1 Colonies	P

"<" means: less than the value shown (below analytical detection limits).

"n/a" means: not applicable.

Table 7. Bacteriological Test Results

Bacteriological Characteristics

Bacteriological testing of selected samples indicated no (zero) coliform bacteria.