

**Seattle Public Schools  
Drinking Water Quality Program**

**Results of Water Quality Testing  
for  
Pathfinder @ Cooper**

Revised September 2, 2019

**General Information:**

Plumbing piping materials: mainly copper

**Remediation plan:**

*This remediation plan is based on a Water Quality policy approved by the School Board. The policy includes standards for the presence of lead, cadmium, copper, iron and other substances in drinking water.*

**Sinks (S in the report) are not considered drinking water sources.** We recognize that there is the potential for students to want to drink from classroom hand-washing sinks, so we test all of those. Where a student's choice to drink from a sink could be a problem, we post a reminder sign, as we do at all restroom sinks.

Status:

Policy Criteria:

All test results meet criteria.

Follow-up monitoring: Will be performed in 2021-2022.

Service: The school will be flushed after any breaks longer than five days.

## Water Quality Testing Results:

### Legend

Symbol	Definition
SE	service entry (main)
B	bubbler
S	sink (faucet)
B/S	sink/bubbler combination
S/B	sink/bubbler combination
ppb	parts per billion
ppm	parts per million
NA	not applicable
None	no action required
Unk	unknown status or action
Sample	sample needs to be taken
Re-test	fixture needs to be resampled
Conf	resample to confirm measurement
No flush	not flushed before sampling
Sink	sampled faucet of S/B combo
Used	recently used; no 1st draw sample possible
PS	post sign
Disable(d)	fixture disabled in response to water quality testing
BDSS	Bubbler disabled, sign on sink
IF	install filter
RB	replace bubbler
RB/IF	replace bubbler and/or install filter
RF	replace faucet
RF/IF	replace faucet and/or install filter
BW	disable fixture and provide bottled water until remediated
Leaks	leaking fixture
NW	not working properly (sample S when B of S/B NW)
OS	out of service - disabled until fixed
RS	return to service - now passes testing
Rem	Removed from system - no longer exists

Table 1. Summary of Results

FIXTURE INFORMATION			LEAD		CADMIUM		COPPER		IRON		OK?
Fixture ID	Type	Location	Pass/Fail	Status	Pass/Fail	Status	Pass/Fail	Status	Pass/Fail	Status	Yes/No/Status
01	S	custodial rm 215	P	None	P	None	P	None	P	None	Yes
06	S	staff lounge	P	None	P	None	P	None	P	None	Yes
07	S	nurses office	P	None	P	None	P	None	P	None	Yes
09	B	hall @ gym, right	P	None	P	None	P	None	P	None	Yes
10	B	hall @ gym - on left	P	None	P	None	P	None	P	None	Yes
11	B/S	music room, room 223	P	None	P	None	P	None	P	None	Yes
12	B	hall @ room 214, left	P	None	P	None	P	None			Yes
13	B	hall @ room 214, right	P	None	P	None	P	None			Yes
14	S/B	room 214	P	None	P	None	P	None	P	None	Yes
15	S/B	room 210	P	None	P	None	P	None	P	None	Yes
16	S/B	room 209	P	None	P	None	P	None	P	None	Yes
17	B	hall @ room 311, left	P	None	P	None	P	None			Yes
18	B	hall @ room 311, right	P	None	P	None	P	None			Yes
19	B/S	room 306	P	None	P	None	P	None			Yes
20	B/S	room 307	P	None	P	None	P	None	P	None	Yes
21	B/S	room 309	P	None	P	None	P	None	P	None	Yes
22	S	room 310	P	None	P	None	P	None	P	None	Yes
24	B	hall @ room 322, left	P	None	P	None	P	None			Yes
25	B	hall @ room 322, right	P	None	P	None	P	None			Yes
26	B/S	room 321	P	None	P	None	P	None			Yes
27	B/S	room 320	P	None	P	None	P	None	P	None	Yes
28	B/S	room 318	P	None	P	None	P	None	P	None	Yes
29	B/S	room 317	P	None	P	None	P	None	P	None	Yes
30	B	hallway - main flr @ elevator - on left	P	None	P	None	P	None	P	None	Yes
31	B	hallway - main flr @ elevator, right	P	None	P	None	P	None			Yes
32	B/S	room 118	P	None	P	None	P	None			Yes
33	B/S	room 119	P	None	P	None	P	None	P	None	Yes
34	B/S	room 121	P	None	P	None	P	None	P	None	Yes
35	B/S	room 122	P	None	P	None	P	None	P	None	Yes
36	B/S	room 123	P	None	P	None	P	None	P	None	Yes
37	B/S	room 124	P	None	P	None	P	None			Yes
39	B/S	room 112	P	None	P	None	P	None			Yes
40	B/S	room 111	P	None	P	None	P	None			Yes
41	B/S	room 110	P	None	P	None	P	None			Yes
42	B/S	room 109	P	None	P	None	P	None	P	None	Yes
43	B/S	room 107	P	None	P	None	P	None	P	None	Yes
44	B/S	room 106	P	None	P	None	P	None	P	None	Yes
49	S	Kitchen sink, left	P	None	P	None	P	None			Yes
50	S	Kitchen sink, right	P	None	P	None	P	None			Yes
53	S	Work room (next to staff lounge)	P	None	P	None	P	None			Yes
58	S	library office	P	None	P	None	P	None			Yes
59	S	room 318, left	P	None	P	None	P	None			Yes
60	S	room 318, right	P	None	P	None	P	None			Yes
61	S	room 317, left	P	None	P	None	P	None	P	None	Yes
62	S	room 317, right	P	None	P	None	P	None			Yes
63	S/B	room 311	P	None	P	None	P	None			Yes
64	S	room 311	P	None	P	None	P	None			Yes
65	S	room 219, work room	P	None	P	None	P	None			Yes

Table 2. Lead Test Results

FIXTURE INFORMATION			1/22/2009			4/28/2012			6/18/2015			8/2/2019			Summary Status	
Fixture ID	Type	Location	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	Pass/Fail	Status
01	S	custodial rm 215	1	<1	P	<1	<1	P	2	<1	P	<1	<1	P	P	None
06	S	staff lounge	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
07	S	nurses office	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
09	B	hall @ gym, right	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
10	B	hall @ gym - on left	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
11	B/S	music room, room 223	5	<1	P	1	<1	P	2	<1	P	<1	<1	P	P	None
12	B	hall @ room 214, left	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
13	B	hall @ room 214, right	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
14	S/B	room 214	<1	<1	P	2	<1	P	<1	<1	P	<1	<1	P	P	None
15	S/B	room 210	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
16	S/B	room 209	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
17	B	hall @ room 311, left	2	1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
18	B	hall @ room 311, right				<1	<1	P	<1	<1	P	1	<1	P	P	None
19	B/S	room 306	2	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
20	B/S	room 307	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
21	B/S	room 309	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
22	S	room 310	<1	<1	P	<1	<1	P	1	1	P	<1	<1	P	P	None
24	B	hall @ room 322, left	8	<1	P	<1	<1	P	1	<1	P	1	<1	P	P	None
25	B	hall @ room 322, right	1	<1	P	<1	<1	P	2	<1	P	2	<1	P	P	None
26	B/S	room 321	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
27	B/S	room 320	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
28	B/S	room 318	<1	<1	P	<1	<1	P	1	<1	P	1	<1	P	P	None
29	B/S	room 317	1	<1	P	<1	<1	P	<1	<1	P	2	<1	P	P	None
30	B	hallway - main flr @ elevator - on left	2	<1	P	<1	<1	P	<1	<1	P	2	<1	P	P	None
31	B	hallway - main flr @ elevator, right	2	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
32	B/S	room 118	2	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
33	B/S	room 119				<1	<1	P	<1	<1	P	<1	<1	P	P	None
34	B/S	room 121	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
35	B/S	room 122	2	<1	P	<1	<1	P	1	<1	P	<1	<1	P	P	None
36	B/S	room 123	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
37	B/S	room 124	1	<1	P	<1	<1	P	3	<1	P	<1	<1	P	P	None
39	B/S	room 112	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
40	B/S	room 111	<1	<1	P				2	<1	P	<1	<1	P	P	None
41	B/S	room 110	2	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
42	B/S	room 109	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
43	B/S	room 107	1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
44	B/S	room 106	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
49	S	Kitchen sink, left	<1	<1	P	3	<1	P	2	<1	P	6	<1	P	P	None
50	S	Kitchen sink, right	<1	<1	P	<1	<1	P	3	<1	P	4	<1	P	P	None
53	S	Work room (next to staff lounge)	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
58	S	library office	2	<1	P	2	<1	P	2	1	P	2	<1	P	P	None
59	S	room 318, left				4	<1	P	5	<1	P	3	<1	P	P	None
60	S	room 318, right				4	<1	P	3	<1	P	2	<1	P	P	None
61	S	room 317, left				3	<1	P	<1	<1	P	2	<1	P	P	None
62	S	room 317, right				3	<1	P	1	<1	P	<1	<1	P	P	None
63	S/B	room 311				<1	1	P	<1	<1	P	<1	<1	P	P	None
64	S	room 311				1	<1	P	1	<1	P	<1	<1	P	P	None
65	S	room 219, work room				1	<1	P	1	1	P	<1	<1	P	P	None

Table 3. Cadmium Test Results

FIXTURE INFORMATION			12/20/2007			1/22/2009			4/28/2012			6/18/2015			8/2/2019			Summary Status	
Fixture ID	Type	Location	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	Pass/Fail	Status
01	S	custodial rm 215				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
06	S	staff lounge				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
07	S	nurses office				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
09	B	hall @ gym, right	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
10	B	hall @ gym - on left	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
11	B/S	music room, room 223				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
12	B	hall @ room 214, left				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
13	B	hall @ room 214, right				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
14	S/B	room 214				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
15	S/B	room 210					<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
16	S/B	room 209				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
17	B	hall @ room 311, left				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
18	B	hall @ room 311, right							<1	<1	P	<1	<1	P	<1	<1	P	P	None
19	B/S	room 306				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
20	B/S	room 307				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
21	B/S	room 309				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
22	S	room 310				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
24	B	hall @ room 322, left				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
25	B	hall @ room 322, right				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
26	B/S	room 321				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
27	B/S	room 320				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
28	B/S	room 318				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
29	B/S	room 317				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
30	B	hallway - main flr @ elevator - on left				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
31	B	hallway - main flr @ elevator, right				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
32	B/S	room 118				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
33	B/S	room 119							<1	<1	P	<1	<1	P	<1	<1	P	P	None
34	B/S	room 121				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
35	B/S	room 122				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
36	B/S	room 123				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
37	B/S	room 124				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
39	B/S	room 112				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
40	B/S	room 111				<1	<1	P				<1	<1	P	<1	<1	P	P	None
41	B/S	room 110				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
42	B/S	room 109				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
43	B/S	room 107				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
44	B/S	room 106				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
49	S	Kitchen sink, left				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
50	S	Kitchen sink, right				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
53	S	Work room (next to staff lounge)				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
58	S	library office				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
59	S	room 318, left							<1	<1	P	<1	<1	P	<1	<1	P	P	None
60	S	room 318, right							<1	<1	P	<1	<1	P	<1	<1	P	P	None
61	S	room 317, left							<1	<1	P	<1	<1	P	<1	<1	P	P	None
62	S	room 317, right							<1	<1	P	<1	<1	P	<1	<1	P	P	None
63	S/B	room 311							<1	<1	P	<1	<1	P	<1	<1	P	P	None
64	S	room 311							<1	<1	P	<1	<1	P	<1	<1	P	P	None
65	S	room 219, work room							<1	<1	P	<1	<1	P	<1	<1	P	P	None

Table 4. Copper Test Results

FIXTURE INFORMATION			1/22/2009			4/28/2012			6/18/2015			8/2/2019			Summary Status	
Fixture ID	Type	Location	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	Pass/Fail	Status
01	S	custodial rm 215	0.216	0.017	P	0.134	0.138	P	0.175	0.176	P	0.077	0.038	P	P	None
06	S	staff lounge	0.207	0.024	P	0.118	0.138	P	0.109	0.097	P	0.06	0.071	P	P	None
07	S	nurses office	0.039	0.028	P	0.202	0.053	P	0.127	0.169	P	0.12	0.08	P	P	None
09	B	hall @ gym, right	0.267	0.252	P	0.165	0.168	P	0.142	0.147	P	0.093	0.09	P	P	None
10	B	hall @ gym - on left	0.254	0.256	P	0.169	0.167	P	0.139	0.112	P	0.086	0.078	P	P	None
11	B/S	music room, room 223	0.306	0.147	P	0.185	0.194	P	0.124	0.146	P	0.1	0.031	P	P	None
12	B	hall @ room 214, left	0.276	0.138	P	0.104	0.067	P	0.123	0.079	P	0.132	0.081	P	P	None
13	B	hall @ room 214, right	0.186	0.099	P	0.134	0.125	P	0.134	0.117	P	0.074	0.047	P	P	None
14	S/B	room 214	0.243	0.211	P	0.14	0.158	P	0.121	0.104	P	0.141	0.09	P	P	None
15	S/B	room 210		0.235	P	0.135	0.08	P	0.138	0.107	P	0.077	0.055	P	P	None
16	S/B	room 209	0.133	0.108	P	0.084	0.056	P	0.112	0.111	P	0.157	0.049	P	P	None
17	B	hall @ room 311, left	0.469	0.351	P	0.178	0.136	P	0.129	0.102	P	0.169	0.074	P	P	None
18	B	hall @ room 311, right				0.159	0.158	P	0.128	0.094	P	0.139	0.062	P	P	None
19	B/S	room 306	0.218	0.191	P	0.164	0.129	P	0.133	0.123	P	0.123	0.102	P	P	None
20	B/S	room 307	0.301	0.239	P	0.174	0.157	P	0.132	0.165	P	0.14	0.118	P	P	None
21	B/S	room 309	0.384	0.277	P	0.169	0.151	P	0.13	0.129	P	0.143	0.128	P	P	None
22	S	room 310	0.325	0.277	P	0.146	0.141	P	0.104	0.111	P	0.097	0.085	P	P	None
24	B	hall @ room 322, left	0.302	0.222	P	0.182	0.201	P	0.144	0.13	P	0.172	0.077	P	P	None
25	B	hall @ room 322, right	0.27	0.203	P	0.2	0.176	P	0.164	0.124	P	0.147	0.083	P	P	None
26	B/S	room 321	0.285	0.152	P	0.145	0.086	P	0.11	0.076	P	0.064	0.059	P	P	None
27	B/S	room 320	0.311	0.259	P	0.176	0.145	P	0.135	0.163	P	0.118	0.107	P	P	None
28	B/S	room 318	0.277	0.204	P	0.129	0.112	P	0.114	0.108	P	0.086	0.051	P	P	None
29	B/S	room 317	0.322	0.176	P	0.184	0.117	P	0.128	0.105	P	0.099	0.094	P	P	None
30	B	hallway - main flr @ elevator - on left	0.313	0.192	P	0.131	0.101	P	0.107	0.09	P	0.079	0.051	P	P	None
31	B	hallway - main flr @ elevator, right	0.245	0.105	P	0.138	0.116	P	0.106	0.093	P	0.08	0.068	P	P	None
32	B/S	room 118	0.262	0.151	P	0.15	0.13	P	0.11	0.105	P	0.088	0.068	P	P	None
33	B/S	room 119				0.196	0.164	P	0.15	0.141	P	0.155	0.091	P	P	None
34	B/S	room 121	0.286	0.233	P	0.156	0.16	P	0.147	0.138	P	0.116	0.102	P	P	None
35	B/S	room 122	0.235	0.148	P	0.131	0.113	P	0.098	0.076	P	0.072	0.046	P	P	None
36	B/S	room 123	0.172	0.14	P	0.139	0.122	P	0.053	0.052	P	0.056	0.05	P	P	None
37	B/S	room 124	0.287	0.247	P	0.163	0.155	P	0.234	0.298	P	0.092	0.14	P	P	None
39	B/S	room 112	0.356	0.368	P	0.174	0.182	P	0.14	0.155	P	0.185	0.264	P	P	None
40	B/S	room 111	0.272	0.224	P				0.115	0.113	P	0.078	0.067	P	P	None
41	B/S	room 110	0.299	0.188	P	0.147	0.148	P	0.09	0.081	P	0.108	0.086	P	P	None
42	B/S	room 109	0.31	0.289	P	0.188	0.171	P	0.183	0.176	P	0.176	0.184	P	P	None
43	B/S	room 107	0.461	0.281	P	0.225	0.157	P	0.159	0.128	P	0.109	0.097	P	P	None
44	B/S	room 106	0.258	0.238	P	0.156	0.088	P	0.084	0.068	P	0.087	0.098	P	P	None
49	S	Kitchen sink, left	0.157	0.167	P	0.232	0.139	P	0.109	0.075	P	0.129	0.05	P	P	None
50	S	Kitchen sink, right	0.16	0.15	P	0.233	0.122	P	0.201	0.088	P	0.151	0.052	P	P	None
53	S	Work room (next to staff lounge)	0.291	0.316	P	0.222	0.249	P	0.154	0.21	P	0.186	0.204	P	P	None
58	S	library office	0.293	0.289	P	0.217	0.232	P	0.212	0.27	P	0.192	0.194	P	P	None
59	S	room 318, left				0.103	0.105	P	0.094	0.09	P	0.142	0.075	P	P	None
60	S	room 318, right				0.114	0.111	P	0.081	0.081	P	0.062	0.048	P	P	None
61	S	room 317, left				0.094	0.097	P	0.08	0.077	P	0.13	0.069	P	P	None
62	S	room 317, right				0.127	0.09	P	0.081	0.074	P	0.109	0.075	P	P	None
63	S/B	room 311				0.179	0.131	P	0.144	0.125	P	0.15	0.084	P	P	None
64	S	room 311				0.141	0.042	P	0.138	0.13	P	0.16	0.097	P	P	None
65	S	room 219, work room				0.142	0.186	P	0.126	0.173	P	0.077	0.008	P	P	None

Table 5. Iron Test Results

FIXTURE INFORMATION			1/22/2009		4/28/2012		6/18/2015		8/2/2019		Summary Status	
Fixture ID	Type	Location	Flush 2m	Pass/Fail	Flush 2m	Pass/Fail	Flush 2m	Pass/Fail	Flush 2m	Pass/Fail	Pass/Fail	Status
01	S	custodial rm 215									P	None
06	S	staff lounge									P	None
07	S	nurses office									P	None
09	B	hall @ gym, right	<0.05	P	<0.05	P					P	None
10	B	hall @ gym - on left					<0.05	P			P	None
11	B/S	music room, room 223							<0.05	P	P	None
12	B	hall @ room 214, left										
13	B	hall @ room 214, right										
14	S/B	room 214	<0.05	P	<0.05	P					P	None
15	S/B	room 210					<0.05	P			P	None
16	S/B	room 209							<0.05	P	P	None
17	B	hall @ room 311, left										
18	B	hall @ room 311, right										
19	B/S	room 306										
20	B/S	room 307	<0.05	P	<0.05	P					P	None
21	B/S	room 309					<0.05	P			P	None
22	S	room 310							<0.05	P	P	None
24	B	hall @ room 322, left										
25	B	hall @ room 322, right										
26	B/S	room 321										
27	B/S	room 320									P	None
28	B/S	room 318	<0.05	P	<0.05	P					P	None
29	B/S	room 317					<0.05	P			P	None
30	B	hallway - main flr @ elevator - on left							<0.05	P	P	None
31	B	hallway - main flr @ elevator, right										
32	B/S	room 118										
33	B/S	room 119									P	None
34	B/S	room 121	<0.05	P	<0.05	P					P	None
35	B/S	room 122					<0.05	P			P	None
36	B/S	room 123							<0.05	P	P	None
37	B/S	room 124										
39	B/S	room 112										
40	B/S	room 111										
41	B/S	room 110										
42	B/S	room 109	<0.05	P	<0.05	P					P	None
43	B/S	room 107					<0.05	P			P	None
44	B/S	room 106							<0.05	P	P	None
49	S	Kitchen sink, left										
50	S	Kitchen sink, right										
53	S	Work room (next to staff lounge)										
58	S	library office										
59	S	room 318, left										
60	S	room 318, right										
61	S	room 317, left							<0.05	P	P	None
62	S	room 317, right										
63	S/B	room 311										
64	S	room 311										
65	S	room 219, work room										

Table 6. Service Entry Test Results

Test Results (Service Entry/SE, Units as Shown)						
SOURCE INFORMATION			Most Recent Sampling			
Fixture ID	Type	Location	Item	Sampled	Max Value	Pass/Fail
00	SE	boiler room 216	Arsenic	18-Jun-15	2 ppb	P
00	SE	boiler room 216	Cadmium	02-Aug-19	1 ppb	P
00	SE	boiler room 216	Chlorine	22-Apr-04	1 ppm	P
00	SE	boiler room 216	Copper	02-Aug-19	0.009 ppm	P
00	SE	boiler room 216	E coli	22-Apr-04	<1 Colonies	P
00	SE	boiler room 216	Iron	02-Aug-19	<0.05 ppm	P
00	SE	boiler room 216	Lead	02-Aug-19	1 ppb	P
00	SE	boiler room 216	Total Coliforms	22-Jan-09	<1 Colonies	P

"<" means: less than the value shown (below analytical detection limits).

"n/a" means: not applicable.

Table 7. Bacteriological Test Results

**Bacteriological Characteristics**

Bacteriological testing of selected samples indicated no (zero) coliform bacteria.