

**Seattle Public Schools  
Drinking Water Quality Program**

**Results of Water Quality Testing  
for  
HAWTHORNE ELEMENTARY SCHOOL**

Updated September 2, 2019

**General Information:**

Plumbing piping materials: mainly copper

**Remediation plan:**

*This remediation plan is based on a Water Quality policy approved by the School Board. The policy includes standards for the presence of lead, cadmium, copper, iron and other substances in drinking water.*

**Sinks (S in the report) are not considered drinking water sources.** We recognize that there is the potential for students to want to drink from classroom hand-washing sinks, so we test all of those. Where a student's choice to drink from a sink could be a problem, we post a reminder sign, as we do at all restroom sinks.

Status:

Policy Criteria:

There is one source doesn't meet the policy criteria.

Follow-up monitoring: Will be performed in 2021-2022

Service: The school will be flushed after any breaks longer than five days.

## Water Quality Testing Results:

### Legend

Symbol	Definition
SE	service entry (main)
B	bubbler
S	sink (faucet)
B/S	sink/bubbler combination
S/B	sink/bubbler combination
ppb	parts per billion
ppm	parts per million
NA	not applicable
None	no action required
Unk	unknown status or action
Sample	sample needs to be taken
Re-test	fixture needs to be resampled
Conf	resample to confirm measurement
No flush	not flushed before sampling
Sink	sampled faucet of S/B combo
Used	recently used; no 1st draw sample possible
PS	post sign
Disable(d)	fixture disabled in response to water quality testing
BDSS	Bubbler disabled, sign on sink
IF	install filter
RB	replace bubbler
RB/IF	replace bubbler and/or install filter
RF	replace faucet
RF/IF	replace faucet and/or install filter
BW	disable fixture and provide bottled water until remediated
Leaks	leaking fixture
NW	not working properly (sample S when B of S/B NW)
OS	out of service - disabled until fixed
RS	return to service - now passes testing
Rem	Removed from system - no longer exists

Table 1. Summary of Results

FIXTURE INFORMATION			LEAD		CADMIUM		COPPER		IRON		OK?
Fixture ID	Type	Location	Pass/Fail	Status	Pass/Fail	Status	Pass/Fail	Status	Pass/Fail	Status	Yes/No/Status
01	B	hallway between lavs	P	None	P	None	P	None	P	None	Yes
02	BF	hallway between lavs, bottle filler	P	None	P	None	P	None	P	None	Yes
03	B	mid-level hallway, outside flash office	P	None	P	None	P	None	P	None	Yes
04	S/B	FLASH office,	P	None	P	None	P	None	P	None	Yes
05	S/B	staff lounge	P	None	P	None	P	None	P	None	Yes
06	B	mid-level hallway	P	None	P	None	P	None	P	None	Yes
07	S/B	room # 1	P	None	P	None	P	None	P	None	Yes
08	S/B	room # 2	P	None	P	None	P	None	P	None	Yes
09	S/B	room # 3	P	None	P	None	P	None	P	None	Yes
10	S/B	room # 4	P	None	P	None	P	None	P	None	Yes
11	S/B	room # 5	P	None	P	None	P	None	P	None	Yes
12	B	hallway near girls bathroom	P	None	P	None	P	None	P	None	Yes
13	B	hallway near boys bathroom	P	None	P	None	P	None	P	None	Yes
14	B	hallway washing stationm	P	None	P	None	P	None	P	None	Yes
15	B	halllway, outside adult bathroom	P	None	P	None	P	None	P	None	Yes
16	B	hallway washing station	P	None	P	None	P	None	P	None	Yes
17	S/B	room # 6	P	None	P	None	P	None	P	None	Yes
18	S/B	room # 7	P	None	P	None	P	None	P	None	Yes
19	S/B	room # 8	P	None	P	None	P	None	P	None	Yes
20	S/B	room # 9	P	None	P	None	P	None	P	None	Yes
21	S/B	room # 10	P	None	P	None	P	None	P	None	Yes
22	S/B	room # 11	P	None	P	None	P	None	P	None	Yes
23	S/B	room # 12	P	None	P	None	P	None	P	None	Yes
24	S/B	room # 15	P	None	P	None	P	None	P	None	Yes
24A	S	room 15	P	None							Yes
25	S/B	room # 16	P	None	P	None	P	None	P	None	Yes
26	S/B	room # 17	P	None	P	None	P	None	P	None	Yes
27	S/B	room # 18	P	None	P	None	P	None	P	None	Yes
28	S/B	room # 19	P	None	P	None	P	None	P	None	Yes
29	S/B	room # 20	P	None	P	None	P	None	P	None	Yes
30	S/B	room # 21	P	None	P	None	P	None	P	None	Yes
31	S/B	room # 22	P	None	P	None	P	None	P	None	Yes
32	S/B	room # 23	P	None	P	None	P	None	P	None	Yes
34	S	kitchen	P	None	P	None	P	None	P	None	Yes
35	S	nurses office - mid level	P	None	P	None	P	None	P	None	Yes
36	S	main office	P	None	P	None	P	None	P	None	Yes
37	S	resource center rm # 13 (mid level)	P	None	P	None	P	None	P	None	Yes
38	S	resource center rm # 14 (mid level)	P	None	P	None	P	None	P	None	Yes
39	S	A/V room next to Library, 3rd floor	P	None	P	None	P	None	P	None	Yes
45	S	kitchen: right sink of double sink	P	None	P	None	P	None	P	None	Yes
46	S	kitchen: left sink of double sink	P	None	P	None	P	None	P	None	Yes
47	S	room 9	P	None	P	None	P	None			Yes

Table 2. Lead Test Results

FIXTURE INFORMATION			2/3/2009			2/7/2012			5/14/2015			5/16/2018		8/16/2019			Summary Status	
Fixture ID	Type	Location	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	Pass/Fail	Status
01	B	hallway between lavs	<1	<1	P									<1	<1	P	P	None
02	BF	hallway between lavs, bottle filler	<1	<1	P	<1	<1	P	<1	<1	P			<1	<1	P	P	None
03	B	mid-level hallway, outside flash office	<1	1	P	<1	<1	P	<1	<1	P			<1	<1	P	P	None
04	S/B	FLASH office,	3	<1	P	<1	<1	P	<1	<1	P			<1	<1	P	P	None
05	S/B	staff lounge	2	<1	P	3	<1	P	2	<1	P			<1	<1	P	P	None
06	B	mid-level hallway	1	2	P	<1	1	P	<1	<1	P			<1	3	P	P	None
07	S/B	room # 1	3	<1	P	<1	<1	P	2	<1	P			1	<1	P	P	None
08	S/B	room # 2	1	1	P	1	<1	P	1	<1	P			<1	<1	P	P	None
09	S/B	room # 3	4	2	P	2	<1	P	2	<1	P			2	<1	P	P	None
10	S/B	room # 4	1	1	P	1	<1	P	1	<1	P			<1	<1	P	P	None
11	S/B	room # 5	1	1	P	1	<1	P	1	<1	P			<1	<1	P	P	None
12	B	hallway near girls bathroom	1	<1	P	<1	<1	P	<1	<1	P			<1	<1	P	P	None
13	B	hallway near boys bathroom	<1	<1	P	<1	<1	P	<1	<1	P			<1	<1	P	P	None
14	B	hallway washing stationm	1	<1	P	1	<1	P	<1	<1	P			1	<1	P	P	None
15	B	hallway, outside adult bathroom	<1	<1	P	<1	<1	P						<1	<1	P	P	None
16	B	hallway washing station	<1	<1	P	<1	<1	P	<1	<1	P			<1	<1	P	P	None
17	S/B	room # 6	2	1	P	<1	<1	P	2	<1	P			1	<1	P	P	None
18	S/B	room # 7	1	<1	P	<1	<1	P	<1	<1	P			<1	<1	P	P	None
19	S/B	room # 8	1	<1	P	<1	<1	P	1	<1	P			<1	<1	P	P	None
20	S/B	room # 9	1	<1	P	<1	<1	P	2	<1	P			<1	<1	P	P	None
21	S/B	room # 10	2	1	P	5	1	P	1	<1	P			<1	<1	P	P	None
22	S/B	room # 11	1	<1	P	<1	<1	P	<1	<1	P			1	<1	P	P	None
23	S/B	room # 12	1	<1	P	1	<1	P	1	<1	P			<1	<1	P	P	None
24	S/B	room # 15	2	1	P	1	<1	P	<1	<1	P	<1	P	<1	<1	P	P	None
24A	S	room 15										3	P				P	None
25	S/B	room # 16	1	<1	P	1	<1	P	2	<1	P			1	<1	P	P	None
26	S/B	room # 17	<1	<1	P	<1	<1	P	<1	<1	P			<1	<1	P	P	None
27	S/B	room # 18	<1	<1	P	<1	<1	P	<1	<1	P			<1	<1	P	P	None
28	S/B	room # 19	1	<1	P	1	<1	P	1	<1	P			<1	<1	P	P	None
29	S/B	room # 20	1	<1	P	1	<1	P	1	<1	P			2	<1	P	P	None
30	S/B	room # 21	<1	<1	P	<1	<1	P	<1	<1	P			<1	<1	P	P	None
31	S/B	room # 22	<1	<1	P	2	<1	P	2	<1	P			2	<1	P	P	None
32	S/B	room # 23	1	<1	P	2	1	P	<1	<1	P			<1	<1	P	P	None
34	S	kitchen	2	<1	P	4	<1	P	2	<1	P			<1	<1	P	P	None
35	S	nurses office - mid level	<1	<1	P	<1	<1	P	<1	<1	P			<1	<1	P	P	None
36	S	main office	5	<1	P	7	<1	P	11	2				<1	<1	P	P	None
37	S	resource center rm # 13 (mid level)	2	<1	P	2	2	P	3	<1	P			4	<1	P	P	None
38	S	resource center rm # 14 (mid level)	2	<1	P	3	<1	P	3	<1	P			<1	<1	P	P	None
39	S	A/V room next to Library, 3rd floor	6	<1	P	<1	<1	P	3	<1	P			<1	<1	P	P	None
45	S	kitchen: right sink of double sink	<1	<1	P	<1	<1	P	2	<1	P			<1	<1	P	P	None
46	S	kitchen: left sink of double sink	2	<1	P	3	<1	P	<1	<1	P			<1	<1	P	P	None
47	S	room 9	5	1	P	7	<1	P	6	<1	P			1	<1	P	P	None

Table 3. Cadmium Test Results

FIXTURE INFORMATION			2/3/2009			2/7/2012			5/14/2015			8/16/2019			Summary Status	
Fixture ID	Type	Location	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	Pass/Fail	Status
01	B	hallway between lavs	<1	<1	P							<1	<1	P	P	None
02	BF	hallway between lavs, bottle filler	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
03	B	mid-level hallway, outside flash office	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
04	S/B	FLASH office,	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
05	S/B	staff lounge	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
06	B	mid-level hallway	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
07	S/B	room # 1	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
08	S/B	room # 2	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
09	S/B	room # 3	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
10	S/B	room # 4	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
11	S/B	room # 5	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
12	B	hallway near girls bathroom	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
13	B	hallway near boys bathroom	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
14	B	hallway washing stationm	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
15	B	hallway, outside adult bathroom	<1	<1	P	<1	<1	P				<1	<1	P	P	None
16	B	hallway washing station	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
17	S/B	room # 6	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
18	S/B	room # 7	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
19	S/B	room # 8	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
20	S/B	room # 9	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
21	S/B	room # 10	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
22	S/B	room # 11	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
23	S/B	room # 12	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
24	S/B	room # 15	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
25	S/B	room # 16	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
26	S/B	room # 17	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
27	S/B	room # 18	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
28	S/B	room # 19	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
29	S/B	room # 20	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
30	S/B	room # 21	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
31	S/B	room # 22	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
32	S/B	room # 23	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
34	S	kitchen	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
35	S	nurses office - mid level	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
36	S	main office	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
37	S	resource center rm # 13 (mid level)	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
38	S	resource center rm # 14 (mid level)	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
39	S	A/V room next to Library, 3rd floor	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
45	S	kitchen: right sink of double sink	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
46	S	kitchen: left sink of double sink	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
47	S	room 9	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None

Table 4. Copper Test Results

FIXTURE INFORMATION			2/3/2009			2/7/2012			5/14/2015			8/16/2019			Summary Status	
Fixture ID	Type	Location	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	Pass/Fail	Status
01	B	hallway between lavs	0.158	0.101	P							0.046	0.052	P	P	None
02	BF	hallway between lavs, bottle filler	0.199	0.134	P	0.064	0.061	P	0.069	0.09	P	0.054	0.052	P	P	None
03	B	mid-level hallway, outside flash office	0.229	0.367	P	0.122	0.13	P	0.102	0.119	P	0.11	0.117	P	P	None
04	S/B	FLASH office,	0.299	0.078	P	0.226	0.234	P	0.249	0.312	P	0.078	0.049	P	P	None
05	S/B	staff lounge	0.174	0.088	P	0.075	0.064	P	0.082	0.068	P	0.072	0.07	P	P	None
06	B	mid-level hallway	0.128	0.144	P	0.085	0.127	P	0.094	0.111	P	0.158	0.23	P	P	None
07	S/B	room # 1	0.236	0.145	P	0.158	0.143	P	0.148	0.111	P	0.113	0.103	P	P	None
08	S/B	room # 2	0.305	0.273	P	0.203	0.2	P	0.219	0.21	P	0.232	0.207	P	P	None
09	S/B	room # 3	0.24	0.132	P	0.173	0.122	P	0.145	0.102	P	0.127	0.097	P	P	None
10	S/B	room # 4	0.175	0.086	P	0.12	0.102	P	0.104	0.069	P	0.097	0.081	P	P	None
11	S/B	room # 5	0.173	0.13	P	0.104	0.083	P	0.092	0.071	P	0.08	0.07	P	P	None
12	B	hallway near girls bathroom	0.103	0.086	P	0.049	0.048	P	0.041	0.038	P	0.073	0.073	P	P	None
13	B	hallway near boys bathroom	0.115	0.079	P	0.06	0.048	P	0.052	0.042	P	0.055	0.063	P	P	None
14	B	hallway washing stationm	0.129	0.045	P	0.108	0.085	P	0.092	0.097	P	0.082	0.076	P	P	None
15	B	hallway, outside adult bathroom	0.138	0.066	P	0.106	0.036	P				0.082	0.08	P	P	None
16	B	hallway washing station	0.09	0.074	P	0.05	0.046	P	0.068	0.068	P	0.072	0.068	P	P	None
17	S/B	room # 6	0.194	0.065	P	0.118	0.079	P	0.098	0.076	P	0.088	0.064	P	P	None
18	S/B	room # 7	0.227	0.227	P	0.163	0.195	P	0.137	0.138	P	0.113	0.12	P	P	None
19	S/B	room # 8	0.18	0.068	P	0.111	0.054	P	0.095	0.046	P	0.057	0.054	P	P	None
20	S/B	room # 9	0.27	0.085	P	0.262	0.055	P	0.255	0.155	P	0.135	0.095	P	P	None
21	S/B	room # 10	0.156	0.083	P	0.108	0.064	P	0.082	0.053	P	0.074	0.075	P	P	None
22	S/B	room # 11	0.295	0.251	P	0.21	0.197	P	0.202	0.182	P	0.182	0.156	P	P	None
23	S/B	room # 12	0.167	0.069	P	0.116	0.051	P	0.111	0.069	P	0.06	0.058	P	P	None
24	S/B	room # 15	0.186	0.066	P	0.113	0.037	P	0.078	0.039	P	0.049	0.045	P	P	None
24A	S	room 15														
25	S/B	room # 16	0.279	0.228	P	0.207	0.176	P	0.178	0.144	P	0.143	0.129	P	P	None
26	S/B	room # 17	0.015	0.003	P	0.021	0.002	P	0.004	<0.002	P	0.002	<0.002	P	P	None
27	S/B	room # 18	0.166	0.023	P	0.098	0.062	P	0.095	0.078	P	0.069	0.052	P	P	None
28	S/B	room # 19	0.157	0.044	P	0.09	0.051	P	0.092	0.044	P	0.073	0.023	P	P	None
29	S/B	room # 20	0.168	0.056	P	0.086	0.055	P	0.084	0.052	P	0.073	0.026	P	P	None
30	S/B	room # 21	0.219	0.195	P	0.195	0.142	P	0.148	0.118	P	0.166	0.154	P	P	None
31	S/B	room # 22	0.114	0.064	P	0.073	0.062	P	0.117	0.059	P	0.092	0.077	P	P	None
32	S/B	room # 23	0.386	0.283	P	0.158	0.124	P	0.147	0.121	P	0.142	0.085	P	P	None
34	S	kitchen	0.143	0.085	P	0.124	0.034	P	0.146	0.093	P	0.037	0.028	P	P	None
35	S	nurses office - mid level	0.004	0.006	P	0.002	<0.002	P	0.007	0.003	P	0.018	0.005	P	P	None
36	S	main office	0.154	0.075	P	0.115	0.294	P	0.124	0.426	P	0.115	0.091	P	P	None
37	S	resource center rm # 13 (mid level)	0.222	0.061	P	0.072	0.05	P	0.114	0.134	P	0.109	0.086	P	P	None
38	S	resource center rm # 14 (mid level)	0.217	0.063	P	0.145	0.055	P	0.141	0.055	P	0.08	0.052	P	P	None
39	S	A/V room next to Library, 3rd floor	0.171	0.067	P	0.033	0.035	P	0.138	0.116	P	0.084	0.049	P	P	None
45	S	kitchen: right sink of double sink	0.135	0.087	P	0.018	0.017	P	0.076	0.058	P	0.043	0.024	P	P	None
46	S	kitchen: left sink of double sink	0.209	0.082	P	0.08	0.02	P	0.072	0.063	P	0.037	0.027	P	P	None
47	S	room 9	0.531	0.105	P	0.2	0.185	P	0.243	0.375	P	0.225	0.227	P	P	None

Table 5. Iron Test Results

FIXTURE INFORMATION			2/3/2009		2/7/2012		5/14/2015		8/16/2019		Summary Status	
Fixture ID	Type	Location	Flush 2m	Pass/Fail	Flush 2m	Pass/Fail	Flush 2m	Pass/Fail	Flush 2m	Pass/Fail	Pass/Fail	Status
01	B	hallway between lavs									P	None
02	BF	hallway between lavs, bottle filler									P	None
03	B	mid-level hallway, outside flash office									P	None
04	S/B	FLASH office,									P	None
05	S/B	staff lounge									P	None
06	B	mid-level hallway			<0.05	P			<0.05	P	P	None
07	S/B	room # 1	<0.05	P			<0.05	P			P	None
08	S/B	room # 2									P	None
09	S/B	room # 3									P	None
10	S/B	room # 4			<0.05	P					P	None
11	S/B	room # 5	0.053	P			<0.05	P			P	None
12	B	hallway near girls bathroom							0.055	P	P	None
13	B	hallway near boys bathroom									P	None
14	B	hallway washing stationm									P	None
15	B	halllway, outside adult bathroom									P	None
16	B	hallway washing station									P	None
17	S/B	room # 6									P	None
18	S/B	room # 7	<0.05	P							P	None
19	S/B	room # 8									P	None
20	S/B	room # 9									P	None
21	S/B	room # 10									P	None
22	S/B	room # 11			<0.05	P					P	None
23	S/B	room # 12					<0.05	P	<0.05	P	P	None
24	S/B	room # 15									P	None
24A	S	room 15										
25	S/B	room # 16	0.093	P							P	None
26	S/B	room # 17									P	None
27	S/B	room # 18									P	None
28	S/B	room # 19									P	None
29	S/B	room # 20							<0.05	P	P	None
30	S/B	room # 21			<0.05	P					P	None
31	S/B	room # 22					<0.05	P			P	None
32	S/B	room # 23									P	None
34	S	kitchen	0.052	P							P	None
35	S	nurses office - mid level									P	None
36	S	main office									P	None
37	S	resource center rm # 13 (mid level)									P	None
38	S	resource center rm # 14 (mid level)							<0.05	P	P	None
39	S	A/V room next to Library, 3rd floor									P	None
45	S	kitchen: right sink of double sink			<0.05	P					P	None
46	S	kitchen: left sink of double sink					<0.05	P			P	None
47	S	room 9										

Table 6. Service Entry Test Results

<b>Test Results (Service Entry/SE, Units as Shown)</b>						
<b>SOURCE INFORMATION</b>			<b>Most Recent Sampling</b>			
Fixture ID	Type	Location	Item	Sampled	Max Value	Pass/Fail
00	SE	boiler room (mech) sink	Arsenic	03-Feb-09	2 ppb	P
00	SE	boiler room (mech) sink	Cadmium	16-Aug-19	1 ppb	P
00	SE	boiler room (mech) sink	Chlorine	09-Apr-04	0.6 ppm	P
00	SE	boiler room (mech) sink	Copper	16-Aug-19	0.016 ppm	P
00	SE	boiler room (mech) sink	E coli	09-Apr-04	<1 Colonies	P
00	SE	boiler room (mech) sink	Iron	16-Aug-19	<0.05 ppm	P
00	SE	boiler room (mech) sink	Lead	16-Aug-19	1 ppb	P
00	SE	boiler room (mech) sink	Total Coliforms	09-Apr-04	<1 Colonies	P

"<" means: less than the value shown (below analytical detection limits).

"n/a" means: not applicable.

Table 7. Bacteriological Test Results

**Bacteriological Characteristics**

Bacteriological testing of selected samples indicated no (zero) coliform bacteria.