

Seattle Public Schools
Drinking Water Quality Program

Results of Water Quality Testing
for
WEDGWOOD ELEMENTARY SCHOOL

Updated April 4th, 2018

General Information:

Plumbing piping materials: mainly copper

Remediation plan:

This remediation plan is based on a Water Quality policy approved by the School Board. The policy includes standards for the presence of lead, cadmium, copper, iron and other substances in drinking water.

Status:

Policy Criteria: All sources met the policy criteria.

Follow-up monitoring: Will be performed in school year 2020-2021.

Service: The school will be flushed after any breaks longer than five days.

Water Quality Testing Results:

Legend	
Symbol	Definition
SE	service entry (main)
B	bubbler
S	sink (faucet)
B/S	sink/bubbler combination
S/B	sink/bubbler combination
ppb	parts per billion
ppm	parts per million
NA	not applicable
None	no action required
Unk	unknown status or action
Sample	sample needs to be taken
Re-test	fixture needs to be resampled
Conf	resample to confirm measurement
No flush	not flushed before sampling
Sink	sampled faucet of S/B combo
Used	recently used; no 1st draw sample possible
PS	post sign
Disable(d)	fixture disabled in response to water quality testing
IF	install filter
RB	replace bubbler
RB/IF	replace bubbler and/or install filter
RF	replace faucet
RF/IF	replace faucet and/or install filter
BW	disable fixture and provide bottled water until remediated
Leaks	leaking fixture
NW	not working properly (sample S when B of S/B NW)
OS	out of service - disabled until fixed
RS	return to service - now passes testing
Rem	Removed from system - no longer exists

Table 1. Summary of Results

FIXTURE INFORMATION			LEAD		CADMIUM		COPPER		IRON		OK?
Fixture ID	Type	Location	Pass/Fail	Status	Pass/Fail	Status	Pass/Fail	Status	Pass/Fail	Status	Yes/No/Status
02	B	hall near north entrance, lower level	P	None	P	None	P	None	P	None	Yes
03	S/B	classroom # 1	P	None	P	None	P	None	P	None	Yes
04	S/B	classroom # 2	P	None	P	None	P	None	P	None	Yes
05	S/B	classroom # 3	P	None	P	None	P	None	P	None	Yes
06	S/B	classroom # 4	P	None	P	None	P	None	P	None	Yes
07	S/B	classroom # 5	P	None	P	None	P	None	P	None	Yes
08	S/B	classroom # 6	P	None	P	None	P	None	P	None	Yes
09	S/B	classroom # 7	P	None	P	None	P	None	P	None	Yes
10	S/B	classroom # 8	P	None	P	None	P	None			Yes
11	S/B	classroom # 9	P	None	P	None	P	None			Yes
12	S/B	classroom # 10	P	None	P	None	P	None			Yes
13	S/B	classroom # 11	P	None	P	None	P	None			Yes
14	S	nurse's office	P	None	P	None	P	None	P	None	Yes
16	S	library office	P	None	P	None	P	None	P	None	Yes
17	S	office supply room	P	None	P	None	P	None	P	None	Yes
18	S	teacher's lounge	P	None	P	None	P	None	P	None	Yes
19	B	hallway outside gymnasium	P	None	P	None	P	None	P	None	Yes
20	B	hallway outside auditorium	P	None	P	None	P	None			Yes
21	S/B	classroom # 14	P	None	P	None	P	None			Yes
22	S/B	classroom # 16	P	None	P	None	P	None			Yes
23	S/B	classroom # 15	P	None	P	None	P	None			Yes
24	S/B	classroom # 18	P	None	P	None	P	None			Yes
25	S/B	classroom # 17	P	None	P	None	P	None			Yes
26	S/B	classroom # 20	P	None	P	None	P	None			Yes
27	S	classroom # 19	P	None	P	None	P	None			Yes
28	S/B	classroom # 22	P	None	P	None	P	None	P	None	Yes
29	S/B	classroom # 21	P	None	P	None	P	None	P	None	Yes
30	S	kitchen	P	None	P	None	P	None	P	None	Yes

Table 2. Lead Test Results

FIXTURE INFORMATION			Initial Sampling				Follow-up Sampling 1				Follow-up Sampling 2				Follow-up Sampling 3				Follow-up Sampling 4			
Fixture ID	Type	Location	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail
02	B	hall near north entrance, lower level	3/26/2004	2	<1	P	8/19/2004	5	2	P									5/18/2006	17	<1	
03	S/B	classroom # 1	3/26/2004	9	3	P	8/19/2004	4	<1	P									5/18/2006	3	<1	P
04	S/B	classroom # 2	3/26/2004	100	1		8/19/2004	2	<1	P									5/18/2006	5	<1	P
05	S/B	classroom # 3	3/26/2004	960	370		8/19/2004	4	<1	P									5/18/2006	2	<1	P
06	S/B	classroom # 4	3/26/2004	130	65		8/19/2004	8	<1	P									5/18/2006	2	<1	P
07	S/B	classroom # 5	3/26/2004	4	5	P					9/15/2004	2	<1	P					5/18/2006	6	<1	P
08	S/B	classroom # 6	3/26/2004	110	32		8/19/2004	2	<1	P									5/18/2006	2	<1	P
09	S/B	classroom # 7	3/26/2004	11	3		8/19/2004	2	<1	P									5/18/2006	1	<1	P
10	S/B	classroom # 8	3/26/2004	74	3		8/19/2004	3	<1	P									5/18/2006	2	1	P
11	S/B	classroom # 9	3/26/2004	15	6		8/19/2004	2	<1	P									5/18/2006	3	2	P
12	S/B	classroom # 10	3/26/2004	160	23		8/19/2004	3	1	P									5/18/2006	4	<1	P
13	S/B	classroom # 11	3/26/2004	150	6		8/19/2004	2	<1	P									5/18/2006	6	<1	P
14	S	nurse's office	3/26/2004	2	<1	P	8/19/2004	6	<1	P									5/18/2006	2	<1	P
16	S	library office	3/26/2004	120	12		8/19/2004	3	<1	P									5/18/2006	11	1	
17	S	office supply room	3/26/2004	4	<1	P	8/19/2004	13	<1						1/11/2005	4	<1	P	5/18/2006	3	<1	P
18	S	teacher's lounge	3/26/2004	<1	<1	P	8/19/2004	8	1	P									5/18/2006	1	<1	P
19	B	hallway outside gymnasium	3/26/2004	10	<1	P	8/19/2004	2	1	P									5/18/2006	30	2	
20	B	hallway outside auditorium	3/26/2004	12	1		8/19/2004	3	<1	P									5/18/2006	<1	<1	P
21	S/B	classroom # 14	3/26/2004	55	12		8/19/2004	3	<1	P									5/18/2006	4	<1	P
22	S/B	classroom # 16	3/26/2004	270	22		8/19/2004	2	<1	P									5/18/2006	1	<1	P
23	S/B	classroom # 15	3/26/2004	59	11		8/19/2004	3	2	P									5/18/2006	25	2	
24	S/B	classroom # 18	3/26/2004	79	14		8/19/2004	2	<1	P									5/18/2006	<1	<1	P
25	S/B	classroom # 17	3/26/2004	150	31		8/19/2004	2	<1	P									5/18/2006	5	<1	P
26	S/B	classroom # 20	3/26/2004	160	50		8/19/2004	1	<1	P									5/18/2006	6	<1	P
27	S	classroom # 19	3/26/2004	1	<1	P	8/19/2004	2	<1	P									5/18/2006	<1	<1	P
28	S/B	classroom # 22	3/26/2004	31	13		8/19/2004	6	<1	P									5/18/2006	6	<1	P
29	S/B	classroom # 21	3/26/2004	74	4		8/19/2004	2	<1	P									5/18/2006	5	1	P
30	S	kitchen					8/19/2004	3	<1	P									5/18/2006	1	<1	P

Table 2. Lead Test Results (Continued)

FIXTURE INFORMATION			Follow-up Sampling 5				Follow-up Sampling 6				Follow-up Sampling 7				Follow-up Sampling 8				Follow-up Sampling 9				Summary Status	
Fixture ID	Type	Location	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Pass/Fail	Status
02	B	hall near north entrance, lower level	1/9/2007	2	<1	P	10/17/2008	1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
03	S/B	classroom # 1					10/17/2008	1	<1	P	10/14/2011	<1	<1	P	9/9/2014	1	<1	P	3/22/2018	<1	<1	P	P	None
04	S/B	classroom # 2					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
05	S/B	classroom # 3					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
06	S/B	classroom # 4					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	1	<1	P	3/22/2018	<1	<1	P	P	None
07	S/B	classroom # 5					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P					P	None
08	S/B	classroom # 6					10/17/2008	<1	<1	P	10/14/2011	1	<1	P	9/9/2014	2	<1	P	3/22/2018	<1	<1	P	P	None
09	S/B	classroom # 7					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
10	S/B	classroom # 8					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
11	S/B	classroom # 9					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	1	<1	P	3/22/2018	<1	<1	P	P	None
12	S/B	classroom # 10					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	2	<1	P	3/22/2018	<1	<1	P	P	None
13	S/B	classroom # 11	1/9/2007	<1	<1	P	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	1	<1	P	3/22/2018	<1	<1	P	P	None
14	S	nurse's office					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
16	S	library office	1/9/2007	8	<1	P	10/17/2008	3	<1	P	10/14/2011	3	<1	P	9/9/2014	4	<1	P	3/22/2018	4	1	P	P	None
17	S	office supply room					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
18	S	teacher's lounge					10/17/2008	1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1		P	3/22/2018	<1	<1	P	P	None
19	B	hallway outside gymnasium	1/9/2007	<1	<1	P	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
20	B	hallway outside auditorium					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
21	S/B	classroom # 14					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	2	<1	P	3/22/2018	<1	<1	P	P	None
22	S/B	classroom # 16					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	1	<1	P	3/22/2018	<1	<1	P	P	None
23	S/B	classroom # 15	1/9/2007	4	<1	P	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	3	<1	P	3/22/2018	<1	<1	P	P	None
24	S/B	classroom # 18					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	1	<1	P	3/22/2018	<1	<1	P	P	None
25	S/B	classroom # 17					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	1	<1	P	3/22/2018	<1	<1	P	P	None
26	S/B	classroom # 20					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
27	S	classroom # 19					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	2	P	3/22/2018	<1	<1	P	P	None
28	S/B	classroom # 22					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
29	S/B	classroom # 21					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	2	<1	P	3/22/2018	<1	<1	P	P	None
30	S	kitchen					10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None

Table 3. Cadmium Test Results

FIXTURE INFORMATION			Initial Sampling				Follow-up Sampling 1				Follow-up Sampling 2				Follow-up Sampling 3				Follow-up Sampling 4			
Fixture ID	Type	Location	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail
02	B	hall near north entrance, lower level	3/26/2004	<1	<1	P	8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
03	S/B	classroom # 1	3/26/2004	<1	<1	P	8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
04	S/B	classroom # 2					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
05	S/B	classroom # 3					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
06	S/B	classroom # 4					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
07	S/B	classroom # 5	3/26/2004	3	<1	P					9/15/2004	<1	<1	P					5/18/2006	<1	<1	P
08	S/B	classroom # 6					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
09	S/B	classroom # 7					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
10	S/B	classroom # 8					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
11	S/B	classroom # 9					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
12	S/B	classroom # 10					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
13	S/B	classroom # 11					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
14	S	nurse's office					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
16	S	library office					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
17	S	office supply room	3/26/2004	1	<1	P	8/19/2004	<1	<1	P					1/11/2005	<1	<1	P	5/18/2006	<1	<1	P
18	S	teacher's lounge	3/26/2004	<1	<1	P	8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
19	B	hallway outside gymnasium	3/26/2004	<1	<1	P	8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
20	B	hallway outside auditorium					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
21	S/B	classroom # 14					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
22	S/B	classroom # 16					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
23	S/B	classroom # 15					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
24	S/B	classroom # 18					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
25	S/B	classroom # 17					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
26	S/B	classroom # 20					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
27	S	classroom # 19					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
28	S/B	classroom # 22					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
29	S/B	classroom # 21	3/26/2004	3	<1	P	8/19/2004	<1	<1	P									5/18/2006	<1	<1	P
30	S	kitchen					8/19/2004	<1	<1	P									5/18/2006	<1	<1	P

Table 3. Cadmium Test Results (Continued)

FIXTURE INFORMATION			Follow-up Sampling 5				Follow-up Sampling 6				Follow-up Sampling 7				Follow-up Sampling 8				Summary Status	
Fixture ID	Type	Location	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Pass/Fail	Status
02	B	hall near north entrance, lower level	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
03	S/B	classroom # 1	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
04	S/B	classroom # 2	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
05	S/B	classroom # 3	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
06	S/B	classroom # 4	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
07	S/B	classroom # 5	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P					P	None
08	S/B	classroom # 6	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
09	S/B	classroom # 7	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
10	S/B	classroom # 8	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
11	S/B	classroom # 9	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
12	S/B	classroom # 10	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
13	S/B	classroom # 11	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
14	S	nurse's office	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
16	S	library office	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
17	S	office supply room	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
18	S	teacher's lounge	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
19	B	hallway outside gymnasium	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
20	B	hallway outside auditorium	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
21	S/B	classroom # 14	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
22	S/B	classroom # 16	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
23	S/B	classroom # 15	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
24	S/B	classroom # 18	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
25	S/B	classroom # 17	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
26	S/B	classroom # 20	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
27	S	classroom # 19	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
28	S/B	classroom # 22	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
29	S/B	classroom # 21	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None
30	S	kitchen	10/17/2008	<1	<1	P	10/14/2011	<1	<1	P	9/9/2014	<1	<1	P	3/22/2018	<1	<1	P	P	None

Table 4. Copper Test Results

FIXTURE INFORMATION			Initial Sampling				Follow-up Sampling 1				Follow-up Sampling 2				Follow-up Sampling 3				Follow-up Sampling 4			
Fixture ID	Type	Location	Sampled	1st Draw	Flush 2m	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail
02	B	hall near north entrance, lower level	3/26/2004	0.004	0.002	P	8/19/2004	0.52	0.093	P									5/18/2006	0.978	0.107	P
03	S/B	classroom # 1	3/26/2004	0.004	<0.002	P	8/19/2004	0.26	0.24	P									5/18/2006	0.298	0.144	P
04	S/B	classroom # 2																	5/18/2006	0.351	0.237	P
05	S/B	classroom # 3					8/19/2004			P									5/18/2006	0.408	0.288	P
06	S/B	classroom # 4																	5/18/2006	0.353	0.081	P
07	S/B	classroom # 5	3/26/2004	0.008	0.007	P					9/15/2004	0.24	0.14	P					5/18/2006	0.4	0.132	P
08	S/B	classroom # 6					8/19/2004			P									5/18/2006	0.488	0.318	P
09	S/B	classroom # 7																	5/18/2006	0.38	0.115	P
10	S/B	classroom # 8					8/19/2004		0.12	P									5/18/2006	0.366	0.962	P
11	S/B	classroom # 9																	5/18/2006	0.441	0.291	P
12	S/B	classroom # 10					8/19/2004		0.08	P									5/18/2006	0.343	0.095	P
13	S/B	classroom # 11																	5/18/2006	0.375	0.261	P
14	S	nurse's office					8/19/2004		0.084	P									5/18/2006	0.275	0.138	P
16	S	library office					8/19/2004		0.068	P									5/18/2006	0.242	0.062	P
17	S	office supply room	3/26/2004	0.022		P	8/19/2004	1.2	0.045	P					1/11/2005	0.55	0.27	P	5/18/2006	0.209	0.192	P
18	S	teacher's lounge	3/26/2004	0.009		P	8/19/2004	0.47	0.25	P									5/18/2006	0.245	0.1	P
19	B	hallway outside gymnasium	3/26/2004	0.073	<0.002	P	8/19/2004	0.36	0.33	P									5/18/2006	0.405	0.338	P
20	B	hallway outside auditorium																	5/18/2006	0.302	0.217	P
21	S/B	classroom # 14																	5/18/2006	0.286	0.144	P
22	S/B	classroom # 16																	5/18/2006	0.328	0.185	P
23	S/B	classroom # 15																	5/18/2006	0.372	0.159	P
24	S/B	classroom # 18																	5/18/2006	0.228	0.25	P
25	S/B	classroom # 17																	5/18/2006	0.439	0.176	P
26	S/B	classroom # 20																	5/18/2006	0.544	0.265	P
27	S	classroom # 19					8/19/2004	0.12	0.19	P									5/18/2006	0.17	0.19	P
28	S/B	classroom # 22																	5/18/2006	0.709	0.322	P
29	S/B	classroom # 21	3/26/2004	0.05	0.003	P	8/19/2004			P									5/18/2006	0.45	0.261	P
30	S	kitchen					8/19/2004	0.23	0.23	P									5/18/2006	0.207	0.217	P

Table 4. Copper Test Results (Continued)

FIXTURE INFORMATION			Follow-up Sampling 5				Follow-up Sampling 6				Follow-up Sampling 7				Follow-up Sampling 8				Summary Status	
Fixture ID	Type	Location	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Sampled	1st Draw	Flush 30s	Pass /Fail	Pass/Fail	Status
02	B	hall near north entrance, lower level	10/17/2008	0.217	0.084	P	10/14/2011	0.162	0.069	P	9/9/2014	0.238	0.143	P	3/22/2018	0.336	0.196	P	P	None
03	S/B	classroom # 1	10/17/2008	0.147	0.161	P	10/14/2011	0.127	0.106	P	9/9/2014	0.154	0.152	P	3/22/2018	0.227	0.242	P	P	None
04	S/B	classroom # 2	10/17/2008	0.17	0.162	P	10/14/2011	0.137	0.114	P	9/9/2014	0.167	0.169	P	3/22/2018	0.257	0.247	P	P	None
05	S/B	classroom # 3	10/17/2008	0.192	0.195	P	10/14/2011	0.168	0.154	P	9/9/2014	0.215	0.214	P	3/22/2018	0.315	0.322	P	P	None
06	S/B	classroom # 4	10/17/2008	0.166	0.155	P	10/14/2011	0.146	0.086	P	9/9/2014	0.156	0.173	P	3/22/2018	0.219	0.231	P	P	None
07	S/B	classroom # 5	10/17/2008	0.146	0.14	P	10/14/2011	0.149	0.124	P	9/9/2014	0.161	0.174	P					P	None
08	S/B	classroom # 6	10/17/2008	0.167	0.168	P	10/14/2011	0.171	0.192	P	9/9/2014	0.225	0.256	P	3/22/2018	0.286	0.296	P	P	None
09	S/B	classroom # 7	10/17/2008	0.152	0.136	P	10/14/2011	0.127	0.103	P	9/9/2014	0.135	0.15	P	3/22/2018	0.23	0.233	P	P	None
10	S/B	classroom # 8	10/17/2008	0.156	0.13	P	10/14/2011	0.138	0.091	P	9/9/2014	0.152	0.139	P	3/22/2018	0.196	0.179	P	P	None
11	S/B	classroom # 9	10/17/2008	0.182	0.128	P	10/14/2011	0.206	0.188	P	9/9/2014	0.189	0.193	P	3/22/2018	0.316	0.382	P	P	None
12	S/B	classroom # 10	10/17/2008	0.164	0.115	P	10/14/2011	0.138	0.094	P	9/9/2014	0.144	0.106	P	3/22/2018	0.204	0.19	P	P	None
13	S/B	classroom # 11	10/17/2008	0.148	0.147	P	10/14/2011	0.155	0.156	P	9/9/2014	0.195	0.176	P	3/22/2018	0.332	0.314	P	P	None
14	S	nurse's office	10/17/2008	0.163	0.121	P	10/14/2011	0.148	0.111	P	9/9/2014	0.146	0.137	P	3/22/2018	0.223	0.24	P	P	None
16	S	library office	10/17/2008	0.171	0.037	P	10/14/2011	0.202	0.073	P	9/9/2014	0.162	0.081	P	3/22/2018	0.256	0.13	P	P	None
17	S	office supply room	10/17/2008	0.143	0.149	P	10/14/2011	0.122	0.108	P	9/9/2014	0.161	0.12	P	3/22/2018	0.193	0.201	P	P	None
18	S	teacher's lounge	10/17/2008	0.099	0.081	P	10/14/2011	0.105	0.107	P	9/9/2014	0.083		P	3/22/2018	0.141	0.187	P	P	None
19	B	hallway outside gymnasium	10/17/2008	0.16	0.162	P	10/14/2011	0.121	0.12	P	9/9/2014	0.14	0.133	P	3/22/2018	0.226	0.229	P	P	None
20	B	hallway outside auditorium	10/17/2008	0.108	0.094	P	10/14/2011	0.121	0.131	P	9/9/2014	0.109	0.131	P	3/22/2018	0.177	0.172	P	P	None
21	S/B	classroom # 14	10/17/2008	0.152	0.127	P	10/14/2011	0.132	0.109	P	9/9/2014	0.132	0.111	P	3/22/2018	0.182	0.171	P	P	None
22	S/B	classroom # 16	10/17/2008	0.151	0.15	P	10/14/2011	0.143	0.132	P	9/9/2014	0.147	0.14	P	3/22/2018	0.214	0.228	P	P	None
23	S/B	classroom # 15	10/17/2008	0.162	0.118	P	10/14/2011	0.183	0.13	P	9/9/2014	0.162	0.147	P	3/22/2018	0.196	0.182	P	P	None
24	S/B	classroom # 18	10/17/2008	0.166	0.133	P	10/14/2011	0.133	0.14	P	9/9/2014	0.146	0.142	P	3/22/2018	0.237	0.271	P	P	None
25	S/B	classroom # 17	10/17/2008	0.231	0.134	P	10/14/2011	0.17	0.131	P	9/9/2014	0.178	0.114	P	3/22/2018	0.259	0.222	P	P	None
26	S/B	classroom # 20	10/17/2008	0.169	0.133	P	10/14/2011	0.143	0.145	P	9/9/2014	0.144	0.145	P	3/22/2018	0.267	0.29	P	P	None
27	S	classroom # 19	10/17/2008	0.095	0.107	P	10/14/2011	0.098	0.086	P	9/9/2014	0.066	0.063	P	3/22/2018	0.136	0.098	P	P	None
28	S/B	classroom # 22	10/17/2008	0.152	0.164	P	10/14/2011	0.17	0.182	P	9/9/2014	0.176	0.166	P	3/22/2018	0.338	0.307	P	P	None
29	S/B	classroom # 21	10/17/2008	0.178	0.143	P	10/14/2011	0.157	0.142	P	9/9/2014	0.121	0.121	P	3/22/2018	0.253	0.268	P	P	None
30	S	kitchen	10/17/2008	0.129	0.124	P	10/14/2011	0.137	0.157	P	9/9/2014	0.085	0.145	P	3/22/2018	0.174	0.176	P	P	None

Table 5. Iron Test Results

FIXTURE INFORMATION			Initial Sampling				Follow-up Sampling 1				Follow-up Sampling 2				Follow-up Sampling 3			
Fixture ID	Type	Location	Sampled	1st Draw	Flush 2m	Pass/Fail	Sampled	1st Draw	Flush 2m	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail
02	B	hall near north entrance, lower level	3/26/2004	1.1	0.16		8/19/2004	0.19		P								
03	S/B	classroom # 1	3/26/2004	0.19	0.13	P	8/19/2004	<0.05		P								
04	S/B	classroom # 2																
05	S/B	classroom # 3					8/19/2004		<0.05	P								
06	S/B	classroom # 4																
07	S/B	classroom # 5	3/26/2004	0.4	0.29	P					9/15/2004	<0.05	<0.05	P				
08	S/B	classroom # 6					8/19/2004		<0.05	P								
09	S/B	classroom # 7																
10	S/B	classroom # 8																
11	S/B	classroom # 9																
12	S/B	classroom # 10																
13	S/B	classroom # 11																
14	S	nurse's office																
16	S	library office																
17	S	office supply room	3/26/2004	0.36		P	8/19/2004	<0.05	<0.05	P					1/11/2005	<0.05	<0.05	P
18	S	teacher's lounge	3/26/2004	1.9			8/19/2004	0.05	<0.05	P								
19	B	hallway outside gymnasium	3/26/2004	0.59	0.17		8/19/2004	0.06		P								
20	B	hallway outside auditorium																
21	S/B	classroom # 14																
22	S/B	classroom # 16																
23	S/B	classroom # 15																
24	S/B	classroom # 18																
25	S/B	classroom # 17																
26	S/B	classroom # 20																
27	S	classroom # 19																
28	S/B	classroom # 22																
29	S/B	classroom # 21	3/26/2004	2.2	0.38		8/19/2004		<0.05	P								
30	S	kitchen					8/19/2004	0.05	0.18	P								

Table 5. Iron Test Results (continued)

FIXTURE INFORMATION			Follow-up Sampling 4				Follow-up Sampling 5				Follow-up Sampling 6				Follow-up Sampling 7				Summary Status	
Fixture ID	Type	Location	Sampled	1st Draw	Flush 2m	Pass /Fail	Sampled	1st Draw	Flush 2m	Pass /Fail	Sampled	1st Draw	Flush 2m	Pass /Fail	Sampled	1st Draw	Flush 2m	Pass /Fail	Pass/Fail	Status
02	B	hall near north entrance, lower level	10/17/2008		<0.05	P	10/14/2011		<0.05	P									P	None
03	S/B	classroom # 1	10/17/2008		<0.05	P	10/14/2011		<0.05	P									P	None
04	S/B	classroom # 2									9/9/2014		<0.05	P					P	None
05	S/B	classroom # 3									9/9/2014		<0.05	P					P	None
06	S/B	classroom # 4												3/22/2018		<0.05	P	P	None	
07	S/B	classroom # 5	10/17/2008		<0.05	P	10/14/2011		<0.05	P									P	None
08	S/B	classroom # 6									9/9/2014		<0.05	P					P	None
09	S/B	classroom # 7												3/22/2018		<0.05	P	P	None	
10	S/B	classroom # 8																		
11	S/B	classroom # 9																		
12	S/B	classroom # 10																		
13	S/B	classroom # 11																		
14	S	nurse's office	10/17/2008		<0.05	P	10/14/2011		<0.05	P									P	None
16	S	library office									9/9/2014		<0.05	P					P	None
17	S	office supply room												3/22/2018		<0.05	P	P	None	
18	S	teacher's lounge																	P	None
19	B	hallway outside gymnasium																	P	None
20	B	hallway outside auditorium																		
21	S/B	classroom # 14																		
22	S/B	classroom # 16																		
23	S/B	classroom # 15																		
24	S/B	classroom # 18																		
25	S/B	classroom # 17																		
26	S/B	classroom # 20																		
27	S	classroom # 19																		
28	S/B	classroom # 22	10/17/2008		<0.05	P	10/14/2011		<0.05	P									P	None
29	S/B	classroom # 21									9/9/2014		<0.05	P					P	None
30	S	kitchen												3/22/2018		<0.05	P	P	None	

Table 6. Service Entry Test Results

Test Results (Service Entry/SE, Units as Shown)						
SOURCE INFORMATION			Most Recent Sampling			
Fixture ID	Type	Location	Item	Sampled	Max Value	Pass/Fail
00	SE	boiler room	Arsenic	22-Mar-18	2 ppb	P
00	SE	boiler room	Cadmium	22-Mar-18	1 ppb	P
00	SE	boiler room	Chlorine	26-Mar-04	0.1 ppm	P
00	SE	boiler room	Copper	22-Mar-18	0.034 ppm	P
00	SE	boiler room	E coli	26-Mar-04	<1 Colonies	P
00	SE	boiler room	Iron	22-Mar-18	<0.05 ppm	P
00	SE	boiler room	Lead	22-Mar-18	1 ppb	P
00	SE	boiler room	Total Coliforms	14-Oct-11	<1 Colonies	P

"<" means: less than the value shown (below analytical detection limits).

"n/a" means: not applicable.

Table 7. Bacteriological Test Results

Bacteriological Characteristics

Bacteriological testing of selected samples indicated no (zero) coliform bacteria.