

Seattle Public Schools
Drinking Water Quality Program

Results of Water Quality Testing
for
Aki Kurose Middle School

Updated January 18, 2019

General Information:

Plumbing piping materials: mainly copper

Remediation plan:

This remediation plan is based on a Water Quality policy approved by the School Board. The policy includes standards for the presence of lead, cadmium, copper, iron and other substances in drinking water.

Status:

Policy Criteria: All sources meet the policy criteria.

Follow-up monitoring: Will be performed in school year 2020-2021.

Service: The school will be flushed after any breaks longer than five days.

Water Quality Testing Results:

Legend	
Symbol	Definition
SE	service entry (main)
B	bubbler
S	sink (faucet)
B/S	sink/bubbler combination
S/B	sink/bubbler combination
ppb	parts per billion
ppm	parts per million
NA	not applicable
None	no action required
Unk	unknown status or action
Sample	sample needs to be taken
Re-test	fixture needs to be resampled
Conf	resample to confirm measurement
No flush	not flushed before sampling
Sink	sampled faucet of S/B combo
Used	recently used; no 1st draw sample possible
PS	post sign
Disable(d)	fixture disabled in response to water quality testing
IF	install filter
RB	replace bubbler
RB/IF	replace bubbler and/or install filter
RF	replace faucet
RF/IF	replace faucet and/or install filter
BW	disable fixture and provide bottled water until remediated
Leaks	leaking fixture
NW	not working properly (sample S when B of S/B NW)
OS	out of service - disabled until fixed
RS	return to service - now passes testing
Rem	Removed from system - no longer exists

Table 1. Summary of Results

FIXTURE INFORMATION			CURRENT STATUS								OK?
			LEAD		CADMIUM		COPPER		IRON		
Fixture ID	Type	Location	Pass/Fail	Status	Pass/Fail	Status	Pass/Fail	Status	Pass/Fail	Status	Yes/No/Status
01	B	hallway, outside lunchroom	P	None	P	None	P	None	P	None	Yes
02	B	hallway, outside 129	P	None	P	None	P	None	P	None	Yes
03	B	hallway, outside 124	P	None	P	None	P	None	P	None	Yes
04	B	hallway, outside main office	P	None	P	None	P	None	P	None	Yes
05	B	hallway, outside 109	P	None	P	None	P	None	P	None	Yes
06	B	hallway, outside 107	P	None	P	None	P	None	P	None	Yes
07	B	hallway, outside 105	P	None	P	None	P	None	P	None	Yes
08	B	hallway, outside 103	P	None	P	None	P	None	P	None	Yes
09	B	hallway - 2nd floor, outside 203	P	None	P	None	P	None	P	None	Yes
11	B	hallway - 2nd floor, outside 205	P	None	P	None	P	None	P	None	Yes
12	B	hallway - 2nd floor, outside 207	P	None	P	None	P	None	P	None	Yes
13	B	hallway - 2nd floor, outside 214	P	None	P	None	P	None	P	None	Yes
14	B	hallway, outside 140	P	None	P	None	P	None	P	None	Yes
15	B	hallway, gym left	P	None	P	None	P	None	P	None	Yes
16	B	hallway, gym right	P	None	P	None	P	None	P	None	Yes
17	B	cafeteria	P	None	P	None	P	None	P	None	Yes
19	S	room 127 W	P	None	P	None	P	None			Yes
20	S	room 213 W	P	None	P	None	P	None	P	None	Yes
23	S	nurse's office	P	None	P	None	P	None	P	None	Yes
24	S	staff lounge	P	None	P	None	P	None	P	Rem	Yes
28	S	132W, E wall	P	None	P	None	P	None	P	None	Yes
29	S	132W, S wall, E faucet	P	None	P	None	P	None	P	None	Yes
30	S	132W, S wall, W faucet	P	None	P	None	P	None	P	None	Yes
31	S	132W, W wall, N faucet	P	None	P	None	P	None	P	None	Yes
32	S	132W, W wall, S faucet	P	None	P	None	P	None	P	None	Yes
51A	S	kitchen, west wall, left	P	None	P	None	P	None	P	None	Yes
51B	S	kitchen, west wall, right	P	None	P	None	P	None	P	None	Yes
52A	S	kitchen, east wall, left	P	None	P	None	P	None	P	None	Yes
52B	S	kitchen, east wall, right	P	None	P	None	P	None	P	None	Yes
53	S	Sink on east side of wall (other side of 52), left	P	None	P	None	P	None			Yes
54	S	Sink on east side of wall (other side of 52), right	P	None	P	None	P	None	P	None	Yes
55	S	Custodian Lunchroom (North)	P	None	P	None	P	None	P	None	Yes
56	B	Gym (West)	P	None	P	None	P	None	P	None	Yes
57	B	GYM (East)	P	None	P	None	P	None			Yes
58	S	room 133, west wall	P	None	P	None	P	None	P	None	Yes
59	S	Room 131, security office, right, cold water	P	None	P	None	P	None	P	None	Yes
60	S	room 125E	P	None	P	None	P	None			Yes
61	S	room 109, North	P	None	P	None	P	None	P	None	Yes
65	S	staff work room, main office	P	None	P	None	P	None			Yes
66	S	LRC, room 209	P	None	P	None	P	None			Yes
68	K	Kitchen, kettle	P	None	P	None	P	None			Yes
69	S	room 133, east wall	P	None	P	None	P	None			Yes

Table 2. Lead Test Results

Test Results (Lead/Pb, ppb)																			
FIXTURE INFORMATION			7/18/2008			4/1/2009			8/5/2011			8/12/2014			8/14/2018			Summary Status	
Fixture ID	Type	Location	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	Pass/Fail	Status
01	B	hallway, outside lunchroom	2	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
02	B	hallway, outside 129				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
03	B	hallway, outside 124	1	1	P				<1	<1	P	1	1	P	1	<1	P	P	None
04	B	hallway, outside main office	1	1	P				<1	<1	P	<1	<1	P	2	1	P	P	None
05	B	hallway, outside 109	1	1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
06	B	hallway, outside 107	1	<1	P				<1	<1	P				<1	<1	P	P	None
07	B	hallway, outside 105							<1	<1	P	<1	<1	P	2	1	P	P	None
08	B	hallway, outside 103				<1	<1	P				<1	<1	P	<1	<1	P	P	None
09	B	hallway - 2nd floor, outside 203	1	<1	P							1	<1	P	<1	<1	P	P	None
11	B	hallway - 2nd floor, outside 205	2	1	P										<1	<1	P	P	None
12	B	hallway - 2nd floor, outside 207	2	<1	P							<1	<1	P	<1	<1	P	P	None
13	B	hallway - 2nd floor, outside 214				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
14	B	hallway, outside 140							<1	<1	P	<1	<1	P	<1	<1	P	P	None
15	B	hallway, gym left				<1	<1	P	1	<1	P	1	<1	P	<1	<1	P	P	None
16	B	hallway, gym right	1	<1	P				4	<1	P	1	<1	P	<1	<1	P	P	None
17	B	cafeteria	1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
19	S	room 127 W	5	1	P				6	3	P				3	<1	P	P	None
20	S	room 213 W	1	4	P				1	4	P	2	5	P	<1	<1	P	P	None
23	S	nurse's office	1	1	P				7	1	P	6	1	P	2	2	P	P	None
24	S	staff lounge	3	<1	P				3	<1	P	<1	<1	P	<1	<1	P	P	None
28	S	132W, E wall	11	<1					3	<1	P	<1	<1	P	<1	<1	P	P	None
29	S	132W, S wall, E faucet	18	<1					7	<1	P	2	<1	P				P	None
30	S	132W, S wall, W faucet	12	<1					14	<1		6	1	P				P	None
31	S	132W, W wall, N faucet	11	<1					14	<1		<1	<1	P	<1	<1	P	P	None
32	S	132W, W wall, S faucet	2	<1	P				3	<1	P	<1	<1	P	1	<1	P	P	None
51A	S	kitchen, west wall, left	1	<1	P				1	<1	P	2	<1	P	<1	<1	P	P	None
51B	S	kitchen, west wall, right	9	<1	P				5	<1	P	6	<1	P	1	<1	P	P	None
52A	S	kitchen, east wall, left	1	1	P				5	<1	P	6	<1	P	1	<1	P	P	None
52B	S	kitchen, east wall, right	2	<1	P				4	<1	P	6	<1	P	3	<1	P	P	None
53	S	Sink on east side of wall (other side of 52), left	11	1					8	<1	P	7	1	P	5	<1	P	P	None
54	S	Sink on east side of wall (other side of 52), right	<1	1	P				2	<1	P	2	<1	P	<1		P	P	None
55	S	Custodian Lunchroom (North)	2	1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
56	B	Gym (West)	<1	<1	P													P	None
57	B	GYM (East)	<1	<1	P													P	None
58	S	room 133, west wall	3	<1	P				1	<1	P	<1	<1	P	<1	<1	P	P	None
59	S	Room 131, security office, right, cold water	10	1	P				4	<1	P	<1	2	P	<1	<1	P	P	None
60	S	room 125E	6	<1	P				16	44		7	1	P	<1	<1	P	P	None
61	S	room 109, North	2	<1	P				3	<1	P	<1	<1	P	1	<1	P	P	None
65	S	staff work room, main office	<1	<1	P				2	<1	P	2	1	P	2	1	P	P	None
66	S	LRC, room 209	6	<1	P				8	2	P				2	3	P	P	None
68	K	Kitchen, kettle							<1	<1	P	2	<1	P	2	<1	P	P	None
69	S	room 133, east wall	1	<1	P				3	<1	P	3	<1	P	1	<1	P	P	None

Table 3. Cadmium Test Results

Test Results (Cadmium/Cd, ppb)																			
FIXTURE INFORMATION			7/18/2008			4/1/2009			8/5/2011			8/12/2014			8/14/2018			Summary Status	
Fixture ID	Type	Location	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	Pass/Fail	Status
01	B	hallway, outside lunchroom	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
02	B	hallway, outside 129				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
03	B	hallway, outside 124	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
04	B	hallway, outside main office	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
05	B	hallway, outside 109	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
06	B	hallway, outside 107	<1	<1	P				<1	<1	P				<1	<1	P	P	None
07	B	hallway, outside 105							<1	<1	P	<1	<1	P	<1	<1	P	P	None
08	B	hallway, outside 103				<1	<1	P				<1	<1	P	<1	<1	P	P	None
09	B	hallway - 2nd floor, outside 203	<1	<1	P							<1	<1	P	<1	<1	P	P	None
11	B	hallway - 2nd floor, outside 205	<1	<1	P										<1	<1	P	P	None
12	B	hallway - 2nd floor, outside 207	<1	<1	P							<1	<1	P	<1	<1	P	P	None
13	B	hallway - 2nd floor, outside 214				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
14	B	hallway, outside 140							<1	<1	P	<1	<1	P	<1	<1	P	P	None
15	B	hallway, gym left				<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
16	B	hallway, gym right	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
17	B	cafeteria	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
19	S	room 127 W	<1	<1	P				<1	<1	P				<1	<1	P	P	None
20	S	room 213 W	<1	2	P				<1	2	P	<1	<1	P	2	<1	P	P	None
23	S	nurse's office	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
24	S	staff lounge	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
28	S	132W, E wall	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
29	S	132W, S wall, E faucet	<1	<1	P				<1	<1	P	<1	<1	P				P	None
30	S	132W, S wall, W faucet	<1	<1	P				<1	<1	P	<1	<1	P				P	None
31	S	132W, W wall, N faucet	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
32	S	132W, W wall, S faucet	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
51A	S	kitchen, west wall, left	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
51B	S	kitchen, west wall, right	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
52A	S	kitchen, east wall, left	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
52B	S	kitchen, east wall, right	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
53	S	Sink on east side of wall (other side of 52), left	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
54	S	Sink on east side of wall (other side of 52), right	<1	<1	P				<1	<1	P	<1	<1	P	<1			P	None
55	S	Custodian Lunchroom (North)	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
56	B	Gym (West)	<1	<1	P													P	None
57	B	GYM (East)	<1	<1	P													P	None
58	S	room 133, west wall	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
59	S	Room 131, security office, right, cold water	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
60	S	room 125E	<1	<1	P				3	3	P	<1	<1	P	<1	<1	P	P	None
61	S	room 109, North	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
65	S	staff work room, main office	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
66	S	LRC, room 209	<1	<1	P				<1	<1	P				<1	<1	P	P	None
68	K	Kitchen, kettle							<1	<1	P	<1	<1	P	<1	<1	P	P	None
69	S	room 133, east wall	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None

Table 4. Copper Test Results

Test Results (Copper/Cu, ppm)																			
FIXTURE INFORMATION			7/18/2008			4/1/2009			8/5/2011			8/12/2014			8/14/2018			Summary Status	
Fixture ID	Type	Location	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	Pass/Fail	Status
01	B	hallway, outside lunchroom	0.34	0.304	P				0.306	0.262	P	0.369	0.349	P	0.272	0.224	P	P	None
02	B	hallway, outside 129				0.288	0.295	P	0.301	0.286	P	0.288	0.284	P	0.233	0.255	P	P	None
03	B	hallway, outside 124	0.154	0.159	P				0.16	0.219	P	0.234	0.258	P	0.129	0.156	P	P	None
04	B	hallway, outside main office	0.326	0.21	P				0.379	0.311	P	0.378	0.404	P	0.268	0.278	P	P	None
05	B	hallway, outside 109	0.436	0.417	P				0.454	0.471	P	0.656	0.699	P	0.366	0.463	P	P	None
06	B	hallway, outside 107	0.381	0.323	P				0.38	0.397	P				0.45	0.492	P	P	None
07	B	hallway, outside 105							0.394	0.407	P	0.466	0.434	P	0.451	0.34	P	P	None
08	B	hallway, outside 103				0.36	0.362	P				0.314	0.305	P	0.293	0.226	P	P	None
09	B	hallway - 2nd floor, outside 203	0.426	0.324	P							0.344	0.354	P	0.254	0.322	P	P	None
11	B	hallway - 2nd floor, outside 205	0.375	0.358	P										0.392	0.357	P	P	None
12	B	hallway - 2nd floor, outside 207	0.406	0.316	P							0.428	0.433	P	0.363	0.419	P	P	None
13	B	hallway - 2nd floor, outside 214				0.396	0.312	P	0.462	0.392	P	0.378	0.33	P	0.29	0.318	P	P	None
14	B	hallway, outside 140							0.347	0.293	P	0.319	0.335	P	0.216	0.277	P	P	None
15	B	hallway, gym left				0.323	0.256	P	0.414	0.294	P	0.299	0.292	P	0.235	0.226	P	P	None
16	B	hallway, gym right	0.335	0.213	P				0.328	0.313	P	0.327	0.29	P	0.28	0.29	P	P	None
17	B	cafeteria	0.268	0.227	P				0.365	0.27	P	0.399	0.3	P	0.389	0.291	P	P	None
19	S	room 127 W	0.206	0.163	P				0.054	0.142	P				0.038	0.127	P	P	None
20	S	room 213 W	0.018	0.022	P				0.015	0.017	P	0.064	0.1	P	0.015	0.102	P	P	None
23	S	nurse's office	0.282	0.304	P				0.279	0.31	P	0.317	0.346	P	0.194	0.197	P	P	None
24	S	staff lounge	0.262	0.26	P				0.278	0.24	P	0.226	0.27	P	0.216	0.179	P	P	None
28	S	132W, E wall	0.249	0.229	P				0.246	0.296	P	0.204	0.247	P	0.262	0.174	P	P	None
29	S	132W, S wall, E faucet	0.231	0.262	P				0.232	0.286	P	0.23	0.244	P				P	None
30	S	132W, S wall, W faucet	0.232	0.246	P				0.184	0.284	P	0.231	0.236	P				P	None
31	S	132W, W wall, N faucet	0.2	0.25	P				0.262	0.288	P	0.229	0.245	P	0.252	0.171	P	P	None
32	S	132W, W wall, S faucet	0.297	0.272	P				0.271	0.298	P	0.22	0.248	P	0.245	0.17	P	P	None
51A	S	kitchen, west wall, left	0.317	0.17	P				0.27	0.056	P	0.229	0.066	P	0.215	0.068	P	P	None
51B	S	kitchen, west wall, right	0.23	0.178	P				0.236	0.132	P	0.17	0.066	P	0.241	0.072	P	P	None
52A	S	kitchen, east wall, left	0.322	0.11	P				0.197	0.122	P	0.271	0.059	P	0.193	0.052	P	P	None
52B	S	kitchen, east wall, right	0.289	0.107	P				0.293	0.038	P	0.276	0.054	P	0.197	0.052	P	P	None
53	S	Sink on east side of wall (other side of 52), left	0.351	0.156	P				0.265	0.04	P	0.186	0.056	P	0.21	0.054	P	P	None
54	S	Sink on east side of wall (other side of 52), right	0.189	0.149	P				0.21	0.034	P	0.144	0.05	P	0.089		P	P	None
55	S	Custodian Lunchroom (North)	0.189	0.136	P				0.186	0.184	P	0.177	0.198	P	0.163	0.119	P	P	None
56	B	Gym (West)	0.338	0.239	P													P	None
57	B	GYM (East)	0.308	0.268	P													P	None
58	S	room 133, west wall	0.334	0.251	P				0.342	0.283	P	0.268	0.268	P	0.229	0.267	P	P	None
59	S	Room 131, security office, right, cold water	0.135	0.194	P				0.082	0.246	P	0.152	0.15	P	0.153	0.126	P	P	None
60	S	room 125E	0.1	0.154	P				0.469	0.66	P	0.098	0.151	P	0.047	0.159	P	P	None
61	S	room 109, North	0.315	0.346	P				0.279	0.292	P	0.372	0.375	P	0.315	0.279	P	P	None
65	S	staff work room, main office	0.28	0.207	P				0.257	0.281	P	0.292	0.369	P	0.248	0.252	P	P	None
66	S	LRC, room 209	0.384	0.474	P				0.368	0.422	P				0.21	0.292	P	P	None
68	K	Kitchen, kettle							0.026	0.025	P	0.306	0.064	P	0.245	0.066	P	P	None
69	S	room 133, east wall	0.282	0.219	P				0.196	0.238	P	0.173	0.212	P	0.2	0.132	P	P	None

Table 5. Iron Test Results

Test Results (Iron/Fe, ppm)												
FIXTURE INFORMATION			7/18/2008		8/5/2011		8/12/2014		8/14/2018		Summary Status	
Fixture ID	Type	Location	Flush 2m	Pass/Fail	Flush 2m	Pass/Fail	Flush 2m	Pass/Fail	Flush 2m	Pass/Fail	Pass/Fail	Status
01	B	hallway, outside lunchroom									P	None
02	B	hallway, outside 129			<0.05	P					P	None
03	B	hallway, outside 124									P	None
04	B	hallway, outside main office									P	None
05	B	hallway, outside 109			<0.05	P					P	None
06	B	hallway, outside 107									P	None
07	B	hallway, outside 105									P	None
08	B	hallway, outside 103					<0.05	P			P	None
09	B	hallway - 2nd floor, outside 203	<0.05	P					<0.05	P	P	None
11	B	hallway - 2nd floor, outside 205	<0.05	P							P	None
12	B	hallway - 2nd floor, outside 207	<0.05	P							P	None
13	B	hallway - 2nd floor, outside 214									P	None
14	B	hallway, outside 140									P	None
15	B	hallway, gym left									P	None
16	B	hallway, gym right			<0.05	P					P	None
17	B	cafeteria									P	None
19	S	room 127 W										
20	S	room 213 W					<0.05	P			P	None
23	S	nurse's office	<0.05	P					<0.05	P	P	None
24	S	staff lounge									P	Rem
28	S	132W, E wall									P	None
29	S	132W, S wall, E faucet									P	None
30	S	132W, S wall, W faucet									P	None
31	S	132W, W wall, N faucet									P	None
32	S	132W, W wall, S faucet									P	None
51A	S	kitchen, west wall, left									P	None
51B	S	kitchen, west wall, right									P	None
52A	S	kitchen, east wall, left									P	None
52B	S	kitchen, east wall, right									P	None
53	S	Sink on east side of wall (other side of 52), left										
54	S	Sink on east side of wall (other side of 52), right					<0.05	P			P	None
55	S	Custodian Lunchroom (North)	<0.05	P					<0.05	P	P	None
56	B	Gym (West)	<0.05	P							P	None
57	B	GYM (East)										
58	S	room 133, west wall					<0.05	P			P	None
59	S	Room 131, security office, right, cold water							<0.05	P	P	None
60	S	room 125E										
61	S	room 109, North	<0.05	P							P	None
65	S	staff work room, main office										
66	S	LRC, room 209										
68	K	Kitchen, kettle										
69	S	room 133, east wall										

Table 6. Service Entry Test Results

Test Results (Service Entry/SE, Units as Shown)						
SOURCE INFORMATION			<i>Most Recent Sampling</i>			
Fixture ID	Type	Location	Item	Sampled	Max Value	Pass/Fail
00	SE	boiler room	Arsenic	14-Aug-18	2 ppb	P
00	SE	boiler room	Cadmium	14-Aug-18	2 ppb	P
00	SE	boiler room	Chlorine	14-Apr-04	0.2 ppm	P
00	SE	boiler room	Copper	14-Aug-18	0.039 ppm	P
00	SE	boiler room	E coli	14-Apr-04	<1 Colonies	P
00	SE	boiler room	Iron	14-Aug-18	0.077 ppm	P
00	SE	boiler room	Lead	14-Aug-18	1 ppb	P
00	SE	boiler room	Total Coliforms	05-Aug-11	<1 Colonies	P

"<" means: less than the value shown (below analytical detection limits).

"n/a" means: not applicable.

Table 7. Bacteriological Test Results

Bacteriological Characteristics

Bacteriological testing of selected samples indicated no (zero) coliform bacteria.