

Table 3. Cadmium Test Results

FIXTURE INFORMATION			Initial Sampling				Follow-up Sampling 1				Follow-up Sampling 2				Follow-up Sampling 3			
Fixture ID	Type	Location	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail
02	S	kitchen, east, right	4/7/2004	<1	<1	P									3/5/2008	<1	<1	P
03	S	kitchen, east, left	4/7/2004	<1	<1	P									3/5/2008	<1	<1	P
05	B	multipurpose room					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
06	S/B	room # 23					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
07	S/B	room # 22					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
08	S/B	room # 21					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
09	S/B	room # 20					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
10	S/B	room # 19	4/7/2004	<1	<1	P									3/5/2008	<1	<1	P
11	S/B	room # 18					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
12	S/B	room # 17					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
13	S/B	room # 16	4/7/2004	<1	<1	P									3/5/2008	<1	<1	P
14	S/B	room # 15					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
15	S/B	room # 14					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
16	S/B	room # 13					5/5/2005		<1	P	7/1/2005	<1		P	3/5/2008	<1	<1	P
17	S/B	room # 12					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
18	S	LCR in office					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
22	B	hallway	4/7/2004	<1	<1	P									3/5/2008	<1	<1	P
23	S/B	room # 24					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
25	S/B	room # 26					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
29	B	hallway					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
30	S	staff work room					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
31	S	staff lounge	4/7/2004	<1	<1	P									3/5/2008	<1	<1	P
32	S/B	room # 11	4/7/2004	<1	<1	P									3/5/2008	<1	<1	P
33	S/B	room # 10					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
34	S/B	room # 9					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
35	S/B	room # 8					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
36	S/B	room # 7					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
37	S/B	room # 6	4/7/2004	<1	<1	P					7/1/2005	<1	<1	P				
38	B	hallway					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
42	S/B	room # 5					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
43	S/B	room # 4					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
44	S/B	room # 1					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
45	S	room # 1					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
46	S/B	room # 2	4/7/2004	<1	<1	P									3/5/2008	<1	<1	P
52	S	nurses office					5/5/2005	<1	<1	P	7/1/2005		<1	P	3/5/2008	<1	<1	P
53	S	room # 3					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P
54	S/B	room #3					5/5/2005	<1	<1	P					3/5/2008	<1	<1	P

Table 3. Cadmium Test Results(continued)

FIXTURE INFORMATION			Follow-up Sampling 4				Follow-up Sampling 5				Follow-up Sampling 6				Follow-up Sampling 7				Summary Status	
Fixture ID	Type	Location	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Pass/Fail	Status
02	S	kitchen, east, right					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
03	S	kitchen, east, left					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
05	B	multipurpose room					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
06	S/B	room # 23					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
07	S/B	room # 22					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
08	S/B	room # 21					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
09	S/B	room # 20					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
10	S/B	room # 19					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
11	S/B	room # 18					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
12	S/B	room # 17					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
13	S/B	room # 16					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
14	S/B	room # 15					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
15	S/B	room # 14					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
16	S/B	room # 13					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
17	S/B	room # 12					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
18	S	LCR in office					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
22	B	hallway					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
23	S/B	room # 24					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
25	S/B	room # 26					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
29	B	hallway					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
30	S	staff work room					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
31	S	staff lounge					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
32	S/B	room # 11					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
33	S/B	room # 10					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
34	S/B	room # 9					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
35	S/B	room # 8					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
36	S/B	room # 7					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
37	S/B	room # 6	6/12/2008	<1	<1	P	2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
38	B	hallway					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
42	S/B	room # 5					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
43	S/B	room # 4					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
45	B	bottle filler at multipurpose room													8/11/2017	<1		P	P	None
52	S	nurses office					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
53	S	room # 3					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None
54	S/B	room #3					2/24/2011	<1	<1	P	4/22/2014	<1	<1	P	8/11/2017	<1	<1	P	P	None

Table 4. Copper Test Results

FIXTURE INFORMATION			Initial Sampling				Follow-up Sampling 1				Follow-up Sampling 2				Follow-up Sampling 3			
Fixture ID	Type	Location	Sampled	1st Draw	Flush 2m	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail
02	S	kitchen, east, right	4/7/2004	0.36		P	5/5/2005		0.065	P					3/5/2008	0.159	0.065	P
03	S	kitchen, east, left	4/7/2004	0.17		P	5/5/2005		0.07	P					3/5/2008	0.215	0.077	P
05	B	multipurpose room					5/5/2005	0.18	0.36	P					3/5/2008	0.166	0.227	P
06	S/B	room # 23					5/5/2005	0.7	0.1	P					3/5/2008	0.248	0.113	P
07	S/B	room # 22					5/5/2005	0.84	0.053	P					3/5/2008	0.281	0.079	P
08	S/B	room # 21					5/5/2005	0.82	0.056	P					3/5/2008	0.236	0.095	P
09	S/B	room # 20					5/5/2005	0.39	0.053	P					3/5/2008	0.224	0.09	P
10	S/B	room # 19	4/7/2004	0.29	0.1	P	5/5/2005		0.14	P					3/5/2008	0.208	0.166	P
11	S/B	room # 18					5/5/2005	0.59	0.042	P					3/5/2008	0.251	0.106	P
12	S/B	room # 17					5/5/2005	0.49	0.16	P					3/5/2008	0.227	0.094	P
13	S/B	room # 16	4/7/2004	0.29	0.095	P	5/5/2005		0.033	P					3/5/2008	0.211	0.151	P
14	S/B	room # 15					5/5/2005	0.052	0.032	P					3/5/2008	0.235	0.091	P
15	S/B	room # 14					5/5/2005	0.065	0.04	P					3/5/2008	0.212	0.091	P
16	S/B	room # 13					5/5/2005		0.044	P	7/1/2005	0.62		P	3/5/2008	0.197	0.101	P
17	S/B	room # 12					5/5/2005	0.2	0.076	P					3/5/2008	0.209	0.112	P
18	S	LCR in office					5/5/2005	0.41	0.15	P					3/5/2008	0.331	0.506	P
22	B	hallway	4/7/2004	0.36	0.12	P	5/5/2005		0.057	P					3/5/2008	0.24	0.178	P
23	S/B	room # 24					5/5/2005	0.43	0.054	P					3/5/2008	0.602	0.171	P
25	S/B	room # 26					5/5/2005	0.42	0.31	P					3/5/2008	0.336	0.225	P
29	B	hallway					5/5/2005	0.27	0.058	P					3/5/2008	0.219	0.113	P
30	S	staff work room					5/5/2005	0.38	0.1	P					3/5/2008	0.3	0.131	P
31	S	staff lounge	4/7/2004	0.24		P	5/5/2005		0.1	P					3/5/2008	0.188	0.126	P
32	S/B	room # 11	4/7/2004	0.29	0.11	P	5/5/2005		0.2	P					3/5/2008	0.208	0.122	P
33	S/B	room # 10					5/5/2005	1.2	0.15	P					3/5/2008	0.224	0.122	P
34	S/B	room # 9					5/5/2005	0.41	0.25	P					3/5/2008	0.252	0.119	P
35	S/B	room # 8					5/5/2005	1	0.099	P					3/5/2008	0.242	0.106	P
36	S/B	room # 7					5/5/2005	0.95	0.17	P					3/5/2008	0.221	0.136	P
37	S/B	room # 6	4/7/2004	0.35	0.12	P	5/5/2005		0.3	P	7/1/2005	0.55	0.2	P				
38	B	hallway					5/5/2005	0.7	0.072	P					3/5/2008	0.288	0.114	P
42	S/B	room # 5					5/5/2005	0.4	0.28	P					3/5/2008	0.244	0.149	P
43	S/B	room # 4					5/5/2005	0.7	0.16	P					3/5/2008	0.238	0.13	P
45	B	bottle filler at multipurpose room																
52	S	nurses office					5/5/2005	0.28	0.13	P	7/1/2005		0.14	P	3/5/2008	0.314	0.157	P
53	S	room # 3					5/5/2005	0.32	0.18	P					3/5/2008	0.252	0.116	P
54	S/B	room #3					5/5/2005	0.78	0.38	P					3/5/2008	0.276	0.14	P

Table 4. Copper Test Results (continued)

FIXTURE INFORMATION			Follow-up Sampling 4				Follow-up Sampling 5				Follow-up Sampling 6				Follow-up Sampling 7				Summary Status	
Fixture ID	Type	Location	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Sampled	1st Draw	Flush 30s	Pass/Fail	Pass/Fail	Status
02	S	kitchen, east, right					2/24/2011	0.045	0.026	P	4/22/2014	0.021	0.016	P	8/11/2017	0.099	0.061	P	P	None
03	S	kitchen, east, left					2/24/2011	0.132	0.022	P	4/22/2014	0.028	0.02	P	8/11/2017	0.077	0.044	P	P	None
05	B	multipurpose room					2/24/2011	0.223	0.236	P	4/22/2014	0.152	0.176	P	8/11/2017	0.057	0.072	P	P	None
06	S/B	room # 23					2/24/2011	0.19	0.045	P	4/22/2014	0.196	0.142	P	8/11/2017	0.117	0.086	P	P	None
07	S/B	room # 22					2/24/2011	0.246	0.095	P	4/22/2014	0.22	0.19	P	8/11/2017	0.186	0.15	P	P	None
08	S/B	room # 21					2/24/2011	0.193	0.091	P	4/22/2014	0.19	0.161	P	8/11/2017	0.151	0.121	P	P	None
09	S/B	room # 20					2/24/2011	0.183	0.051	P	4/22/2014	0.154	0.154	P	8/11/2017	0.102	0.085	P	P	None
10	S/B	room # 19					2/24/2011	0.185	0.184	P	4/22/2014	0.198	0.212	P	8/11/2017	0.098	0.095	P	P	None
11	S/B	room # 18					2/24/2011	0.203	0.13	P	4/22/2014	0.197	0.142	P	8/11/2017	0.093	0.079	P	P	None
12	S/B	room # 17					2/24/2011	0.192	0.08	P	4/22/2014	0.169	0.174	P	8/11/2017	0.093	0.085	P	P	None
13	S/B	room # 16					2/24/2011	0.193	0.174	P	4/22/2014	0.188	0.203	P	8/11/2017	0.099	0.089	P	P	None
14	S/B	room # 15					2/24/2011	0.184	0.072	P	4/22/2014	0.193	0.165	P	8/11/2017	0.093	0.087	P	P	None
15	S/B	room # 14					2/24/2011	0.18	0.081	P	4/22/2014	0.19	0.165	P	8/11/2017	0.11	0.111	P	P	None
16	S/B	room # 13					2/24/2011	0.167	0.111	P	4/22/2014	0.154	0.162	P	8/11/2017	0.136	0.119	P	P	None
17	S/B	room # 12					2/24/2011	0.172	0.116	P	4/22/2014	0.172	0.152	P	8/11/2017	0.128	0.114	P	P	None
18	S	LCR in office					2/24/2011	0.264	0.224	P	4/22/2014	0.514	0.262	P	8/11/2017	0.243	0.131	P	P	None
22	B	hallway					2/24/2011	0.194	0.168	P	4/22/2014	0.201	0.174	P	8/11/2017	0.129	0.108	P	P	None
23	S/B	room # 24					2/24/2011	0.36	0.408	P	4/22/2014	0.368	0.336	P	8/11/2017	0.238	0.218	P	P	None
25	S/B	room # 26					2/24/2011	0.353	0.374	P	4/22/2014	0.276	0.271	P	8/11/2017	0.196	0.189	P	P	None
29	B	hallway					2/24/2011	0.167	0.086	P	4/22/2014	0.181	0.145	P	8/11/2017	0.106	0.094	P	P	None
30	S	staff work room					2/24/2011	0.278	0.392	P	4/22/2014	0.341	0.409	P	8/11/2017	0.226	0.251	P	P	None
31	S	staff lounge					2/24/2011	0.138	0.128	P	4/22/2014	0.152	0.118	P	8/11/2017	0.09	0.09	P	P	None
32	S/B	room # 11					2/24/2011	0.182	0.096	P	4/22/2014	0.261	0.327	P	8/11/2017	0.15	0.12	P	P	None
33	S/B	room # 10					2/24/2011	0.202	0.178	P	4/22/2014	0.202	0.155	P	8/11/2017	0.108	0.097	P	P	None
34	S/B	room # 9					2/24/2011	0.198	0.181	P	4/22/2014	0.209	0.141	P	8/11/2017	0.13	0.073	P	P	None
35	S/B	room # 8					2/24/2011	0.187	0.052	P	4/22/2014	0.207	0.138	P	8/11/2017	0.108	0.075	P	P	None
36	S/B	room # 7					2/24/2011	0.186	0.155	P	4/22/2014	0.221	0.186	P	8/11/2017	0.132	0.111	P	P	None
37	S/B	room # 6	6/12/2008	<0.002	<0.002	P	2/24/2011	<0.002	<0.002	P	4/22/2014	0.173	0.138	P	8/11/2017	0.003	0.003	P	P	None
38	B	hallway					2/24/2011	0.038	0.038	P	4/22/2014	0.232	0.123	P	8/11/2017	0.15	0.112	P	P	None
42	S/B	room # 5					2/24/2011	0.178	0.116	P	4/22/2014	0.209	0.202	P	8/11/2017	0.145	0.11	P	P	None
43	S/B	room # 4					2/24/2011	0.18	0.145	P	4/22/2014	0.202	0.189	P	8/11/2017	0.135	0.087	P	P	None
45	B	bottle filler at multipurpose room													8/11/2017	0.079		P	P	None
52	S	nurses office					2/24/2011	0.172	0.153	P	4/22/2014	0.422	0.173	P	8/11/2017	0.166	0.101	P	P	None
53	S	room # 3					2/24/2011	0.165	0.107	P	4/22/2014	0.217	0.225	P	8/11/2017	0.11	0.074	P	P	None
54	S/B	room #3					2/24/2011	0.215	0.22	P	4/22/2014	0.13	0.115	P	8/11/2017	0.136	0.136	P	P	None

Table 5. Iron Test Results

FIXTURE INFORMATION			Initial Sampling				Follow-up Sampling 1				Follow-up Sampling 2				Follow-up Sampling 3				Follow-up Sampling 4				Follow-up Sampling 5				Summary Status		
Fixture ID	Type	Location	Sampled	1st Draw	Flush 2m	Pass /Fail	Sampled	1st Draw	Flush 2m	Pass /Fail	Sampled	1st Draw	Flush 2m	Pass /Fail	Sampled	1st Draw	Flush 2m	Pass /Fail	Sampled	1st Draw	Flush 2m	Pass /Fail	Sampled	1st Draw	Flush 2m	Pass /Fail	Pass /Fail	Status	
02	S	kitchen, east, right	4/7/2004	<0.05		P	5/5/2005		<0.05	P																P	None		
03	S	kitchen, east, left	4/7/2004	<0.05		P	5/5/2005		<0.05	P													8/11/2017		<0.05	P	P	None	
05	B	multipurpose room					5/5/2005		<0.05	P																	P	None	
06	S/B	room # 23					5/5/2005		<0.05	P																	P	None	
07	S/B	room # 22					5/5/2005		<0.05	P																	P	None	
08	S/B	room # 21					5/5/2005		<0.05	P																	P	None	
09	S/B	room # 20					5/5/2005		<0.05	P																	P	None	
10	S/B	room # 19	4/7/2004	0.06	<0.05	P	5/5/2005		<0.05	P					2/24/2011		<0.05	P									P	None	
11	S/B	room # 18					5/5/2005		<0.05	P										4/22/2014		<0.05	P				P	None	
12	S/B	room # 17					5/5/2005		<0.05	P																	P	None	
13	S/B	room # 16	4/7/2004	<0.05	<0.05	P	5/5/2005		<0.05	P													8/11/2017		<0.05	P	P	None	
14	S/B	room # 15					5/5/2005		<0.05	P																	P	None	
15	S/B	room # 14					5/5/2005		<0.05	P										4/22/2014		<0.05	P				P	None	
16	S/B	room # 13					5/5/2005		<0.05	P																	P	None	
17	S/B	room # 12					5/5/2005		<0.05	P																	P	None	
18	S	LCR in office					5/5/2005		<0.05	P																	P	None	
22	B	hallway	4/7/2004	0.06	<0.05	P	5/5/2005		<0.05	P																	P	None	
23	S/B	room # 24					5/5/2005		<0.05	P																	P	None	
25	S/B	room # 26					5/5/2005		<0.05	P																	P	None	
29	B	hallway					5/5/2005		<0.05	P																	P	None	
30	S	staff work room					5/5/2005		<0.05	P																	P	None	
31	S	staff lounge	4/7/2004	<0.05		P	5/5/2005		<0.05	P																	P	None	
32	S/B	room # 11	4/7/2004	<0.05	<0.05	P	5/5/2005		<0.05	P					2/24/2011		<0.05	P									P	None	
33	S/B	room # 10					5/5/2005		<0.05	P										4/22/2014		<0.05	P				P	None	
34	S/B	room # 9					5/5/2005		<0.05	P													8/11/2017		<0.05	P	P	None	
35	S/B	room # 8					5/5/2005		<0.05	P																	P	None	
36	S/B	room # 7					5/5/2005		<0.05	P																	P	None	
37	S/B	room # 6	4/7/2004	<0.05	<0.05	P	5/5/2005		<0.05	P	7/1/2005		<0.05	P	2/24/2011		<0.05	P									P	None	
38	B	hallway					5/5/2005		<0.05	P										4/22/2014		<0.05	P				P	None	
42	S/B	room # 5					5/5/2005		<0.05	P																	P	None	
43	S/B	room # 4					5/5/2005		<0.05	P																	P	None	
45	B	bottle filler at multipurpose room																											
52	S	nurses office					5/5/2005		<0.05	P										4/22/2014		<0.05	P				P	None	
53	S	room # 3					5/5/2005		<0.05	P																	P	None	
54	S/B	room #3					5/5/2005		<0.05	P																	P	None	

Table 6. Service Entry Test Results

Test Results (Service Entry/SE, Units as Shown)						
SOURCE INFORMATION			Most Recent Sampling			
Fixture ID	Type	Location	Item	Sampled	Max Value	Pass/Fail
00	SE	boiler room	Arsenic	11-Aug-17	2 ppb	P
00	SE	boiler room	Cadmium	11-Aug-17	1 ppb	P
00	SE	boiler room	Copper	11-Aug-17	0.04 ppm	P
00	SE	boiler room	E coli	07-Apr-04	<1 Colonies	P
00	SE	boiler room	Iron	11-Aug-17	<0.05 ppm	P
00	SE	boiler room	Lead	11-Aug-17	1 ppb	P
00	SE	boiler room	Total Coliforms	24-Feb-11	<1 Colonies	P

"<" means: less than the value shown (below analytical detection limits).

"n/a" means: not applicable.

Table 7. Bacteriological Test Results

Bacteriological Characteristics

Bacteriological testing of selected samples indicated no (zero) coliform bacteria.