

**Seattle Public Schools
Drinking Water Quality Program**

**Results of Water Quality Testing
for
Kimball Elementary**

Updated September 3, 2019

General Information:

Plumbing piping materials: mixed galvanized steel and copper

Remediation plan:

This remediation plan is based on a Water Quality policy approved by the School Board. The policy includes standards for the presence of lead, cadmium, copper, iron and other substances in drinking water.

Sinks (S in the report) are not considered drinking water sources. We recognize that there is the potential for students to want to drink from classroom hand-washing sinks, so we test all of those. Where a student's choice to drink from a sink could be a problem, we post a reminder sign, as we do at all restroom sinks.

Status:

Policy Criteria: There are three sources that do not meet the policy criteria. Signs will be posted at: LMC office (south) (#43), LMC office (north) (#44). Area K work room (#41)

Bottled water will be provided at Spec. Ed P8 (#47).

Follow-up monitoring: Will be performed in school year 2021-2022.

Service: The school will be flushed after any breaks longer than five days.

Water Quality Testing Results:

Legend

Symbol	Definition
SE	service entry (main)
B	bubbler
S	sink (faucet)
B/S	sink/bubbler combination
S/B	sink/bubbler combination
ppb	parts per billion
ppm	parts per million
NA	not applicable
None	no action required
Unk	unknown status or action
Sample	sample needs to be taken
Re-test	fixture needs to be resampled
Conf	resample to confirm measurement
No flush	not flushed before sampling
Sink	sampled faucet of S/B combo
Used	recently used; no 1st draw sample possible
PS	post sign
Disable(d)	fixture disabled in response to water quality testing
BDSS	Bubbler disabled, sign on sink
IF	install filter
RB	replace bubbler
RB/IF	replace bubbler and/or install filter
RF	replace faucet
RF/IF	replace faucet and/or install filter
BW	disable fixture and provide bottled water until remediated
Leaks	leaking fixture
NW	not working properly (sample S when B of S/B NW)
OS	out of service - disabled until fixed
RS	return to service - now passes testing
Rem	Removed from system - no longer exists

Table 1. Summary of Results

FIXTURE INFORMATION			LEAD		CADMIUM		COPPER		IRON		OK?
Fixture ID	Type	Location	Pass/Fail	Status	Pass/Fail	Status	Pass/Fail	Status	Pass/Fail	Status	Yes/No/Status
02	S/B	area K	P	None	P	None	P	None	P	None	Yes
03	S/B	area K	P	None	P	None	P	None	P	None	Yes
04	S/B	area K	P	None	P	None	P	None	P	None	Yes
05	S/B	area K	P	None	P	None	P	None	P	None	Yes
06	S/B	area B	P	None	P	None	P	None	P	None	Yes
07	S/B	area B	P	None	P	None	P	None	P	None	Yes
07A	S	Area B near #07	P	None	P	None	P	None	P	None	Yes
08	S/B	area A	P	None	P	None	P	None	P	None	Yes
08A	S	Area B near #08	P	None	P	None	P	None			Yes
09	S/B	area A	P	None	P	None	P	None	P	None	Yes
10	S/B	area D	P	None	P	None	P	None	P	None	Yes
11	S/B	area D (near lav)	P	None	P	None	P	None	P	None	Yes
11A	S	near 11	P	None	P	None	P	None	P	None	Yes
12	S/B	area C (near lav)	P	None	P	None	P	None	P	None	Yes
12A	S	near 12	P	None	P	None	P	None			Yes
13	S/B	area C	P	None	P	None	P	None	P	None	Yes
14	S/B	off gym	P	None	P	None	P	None	P	None	Yes
14A	S	off gym	P	None	P	None	P	None			Yes
14B	S	off gym	P	None	P	None	P	None	P	None	Yes
15	S	portable # 4	P	None	P	None	P	None	P	None	Yes
16	B	womens portable restroom	P	None	P	None	P	None	P	None	Yes
17	B	womens portable restroom	P	None	P	None	P	None	P	None	Yes
18	B	womens portable restroom	P	None	P	None	P	None	P	None	Yes
19	B	womens portable restroom	P	None	P	None	P	None	P	None	Yes
20	B	mens portable restroom	P	None	P	None	P	None	P	None	Yes
21	B	mens portable restroom	P	None	P	None	P	None	P	None	Yes
22	B	mens portable restroom	P	None	P	None	P	None	P	None	Yes
23	B	mens portable restroom	P	None	P	None	P	None	P	None	Yes
25	S	area E	P	None	P	None	P	None	P	None	Yes
26	S	area E	P	None	P	None	P	None	P	None	Yes
27	S	area E	P	None	P	None	P	None	P	None	Yes
31	S	kitchen	P	None	P	None	P	None	P	None	Yes
32	S	area D coffee room	P	None	P	None	P	None	P	None	Yes
33	S	area C work room	P	None	P	None	P	None	P	None	Yes
34	S	commons kitchen	P	None	P	None	P	None	P	None	Yes
35	S	teachers lounge	P	None	P	None	P	None	P	None	Yes
36	S	nurses office	P	None	P	None	P	None	P	None	Yes
37	S	office room sink	P	None	P	None	P	None	P	None	Yes
40	S	Area K north-east corner	P	None	P	None	P	None			Yes
41	S	Area K workroom	F	PS	P	None	P	None			PS
42	S	A.B workroom	P	None	P	None	P	None			Yes
43	S	LMC office (south)	F	PS	P	None	P	None			PS
44	S	LMC office (north)	F	PS	P	None	P	None	P	None	PS
45	S	Area E (South east)	P	None	P	None	P	None	P	None	Yes
46	S	P7	P	None	P	None	P	None	P	None	Yes
47	S/B	P8	P	None	P	None	P	None			Yes
48	S	P2	P	None	P	None	P	None	P	None	Yes

Table 2. Lead Test Results

FIXTURE INFORMATION			4/25/2012			9/19/2012			5/28/2015			9/15/2016			2/20/2019			8/29/2019			Summary Status	
Fixture ID	Type	Location	1st Draw	Flush 30s	Pass /Fail	1st Draw	Flush 30s	Pass /Fail	1st Draw	Flush 30s	Pass /Fail	1st Draw	Flush 30s	Pass /Fail	1st Draw	Flush 30s	Pass /Fail	1st Draw	Flush 30s	Pass /Fail	Pass/Fail	Status
02	S/B	area K	3	2	P				1	<1	P				1	<1	P				P	None
03	S/B	area K	2	2	P				2	1	P				2	<1	P				P	None
04	S/B	area K	2	<1	P				6	<1	P				4	<1	P				P	None
05	S/B	area K	2	<1	P				6	3	P				2	<1	P				P	None
06	S/B	area B	1	<1	P				1	1	P				<1	<1	P				P	None
07	S/B	area B	1	<1	P				<1	<1	P				<1	1	P				P	None
07A	S	Area B near #07	3	1	P				2	1	P				2	<1	P				P	None
08	S/B	area A	<1	<1	P				1	<1	P				1	<1	P				P	None
08A	S	Area B near #08	3	<1	P				2	<1	P				<1	<1	P				P	None
09	S/B	area A	2	1	P				1	2	P				1	1	P				P	None
10	S/B	area D	2	<1	P				2	<1	P				1	<1	P				P	None
11	S/B	area D (near lav)	<1	7	P				1	<1	P				1	1	P				P	None
11A	S	near 11	2	3	P				2	4	P				2	4	P				P	None
12	S/B	area C (near lav)	<1	<1	P				<1	<1	P				<1	<1	P				P	None
12A	S	near 12	5	<1	P				6	1	P				2	1	P				P	None
13	S/B	area C	3	4	P				7	4	P				7	<1	P				P	None
14	S/B	off gym	3	<1	P				3	<1	P										P	None
14A	S	off gym	4	<1	P				7	<1	P										P	None
14B	S	off gym	<1	<1	P				<1	<1	P										P	None
15	S	portable # 4	3	2	P				4	5	P	3	<1	P	<1	<1	P				P	None
16	B	womens portable restroom	<1	<1	P	<1	<1	P	<1	<1	P				<1	<1	P				P	None
17	B	womens portable restroom	<1	<1	P	<1	<1	P	<1	<1	P				<1	<1	P				P	None
18	B	womens portable restroom	<1	<1	P	1	<1	P	<1	<1	P				<1	<1	P				P	None
19	B	womens portable restroom	<1	<1	P	<1	<1	P	<1	<1	P				<1	<1	P				P	None
20	B	mens portable restroom	<1	<1	P				<1	<1	P				<1	<1	P				P	None
21	B	mens portable restroom	<1	<1	P				<1	<1	P				<1	<1	P				P	None
22	B	mens portable restroom	<1	<1	P				<1	<1	P				<1	<1	P				P	None
23	B	mens portable restroom	<1	<1	P				<1	<1	P				<1	<1	P				P	None
25	S	area E	<1	<1	P				<1	<1	P				<1	<1	P				P	None
26	S	area E	<1	<1	P				<1	<1	P				<1	<1	P				P	None
27	S	area E	<1	<1	P				<1	<1	P				<1	<1	P				P	None
31	S	kitchen	3	<1	P				3	<1	P				1	<1	P				P	None
32	S	area D coffee room	14	2					16	2					6	2	P	4	2	P	P	None
33	S	area C work room	5	1	P				7	2	P				2	<1	P				P	None
34	S	commons kitchen	<1	<1	P				<1	<1	P				<1	<1	P				P	None
35	S	teachers lounge	<1	<1	P				<1	<1	P				<1	<1	P				P	None
36	S	nurses office	8	2	P				2	<1	P				4	1	P				P	None
37	S	office room sink	2	<1	P				3	<1	P				2	<1	P				P	None
40	S	Area K north-east corner	1	<1	P				2	<1	P				2	<1	P				P	None
41	S	Area K workroom	24	1					21	4					9	1	P	16	2		F	PS
42	S	A.B workroom	1	<1	P				1	1	P				<1	<1	P				P	None
43	S	LMC office (south)	16	9					21	15					14	7		12	2		F	PS
44	S	LMC office (north)	30	9					33	7					34	9		12	5		F	PS
45	S	Area E (South east)	<1	<1	P				<1	<1	P				<1	<1	P				P	None
46	S	P7	1	2	P				2	2	P				<1	2	P				P	None
47	S/B	P8	<1	<1	P				<1	<1	P				<1	<1	P				P	None
48	S	P2	<1	<1	P				<1	1	P										P	None

Table 3. Cadmium Test Results

FIXTURE INFORMATION			2/24/2009			4/25/2012			9/19/2012			5/28/2015			9/15/2016			2/20/2019			Summary Status	
Fixture ID	Type	Location	1st Draw	Flush 30s	Pass /Fail	1st Draw	Flush 30s	Pass /Fail	1st Draw	Flush 30s	Pass /Fail	1st Draw	Flush 30s	Pass /Fail	1st Draw	Flush 30s	Pass /Fail	1st Draw	Flush 30s	Pass /Fail	Pass/Fail	Status
02	S/B	area K	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
03	S/B	area K	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
04	S/B	area K	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
05	S/B	area K	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
06	S/B	area B	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
07	S/B	area B	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
07A	S	Area B near #07	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
08	S/B	area A	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
08A	S	Area B near #08	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
09	S/B	area A	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
10	S/B	area D	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
11	S/B	area D (near lav)	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
11A	S	near 11	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
12	S/B	area C (near lav)	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
12A	S	near 12	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
13	S/B	area C	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
14	S/B	off gym	<1	<1	P	<1	<1	P				<1	<1	P							P	None
14A	S	off gym	<1	<1	P	<1	<1	P				<1	<1	P							P	None
14B	S	off gym	<1	<1	P	<1	<1	P				<1	<1	P							P	None
15	S	portable # 4	<1	<1	P	<1	2	P				2	3	P	<1	<1	P	<1	<1	P	P	None
16	B	womens portable restroom	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P				<1	<1	P	P	None
17	B	womens portable restroom				<1	<1	P	<1	<1	P	<1	<1	P				<1	<1	P	P	None
18	B	womens portable restroom				<1	<1	P	<1	<1	P	<1	<1	P				<1	<1	P	P	None
19	B	womens portable restroom				<1	<1	P	<1	<1	P	<1	<1	P				<1	<1	P	P	None
20	B	mens portable restroom	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
21	B	mens portable restroom				<1	<1	P				<1	<1	P				<1	<1	P	P	None
22	B	mens portable restroom	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
23	B	mens portable restroom	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
25	S	area E	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
26	S	area E	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
27	S	area E	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
31	S	kitchen	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
32	S	area D coffee room	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
33	S	area C work room	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
34	S	commons kitchen	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
35	S	teachers lounge	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
36	S	nurses office	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
37	S	office room sink	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
40	S	Area K north-east corner	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
41	S	Area K workroom	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
42	S	A.B workroom	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
43	S	LMC office (south)	8	<1		<1	<1	P				<1	<1	P				<1	<1	P	P	None
44	S	LMC office (north)	<1	<1	P	6	<1					6	<1					<1	<1	P	P	None
45	S	Area E (South east)	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
46	S	P7	<1	<1	P	1	<1	P				<1	<1	P				<1	<1	P	P	None
47	S/B	P8	<1	<1	P	<1	<1	P				<1	<1	P				<1	<1	P	P	None
48	S	P2	<1	<1	P	<1	<1	P				<1	<1	P							P	None

Table 4. Copper Test Results

FIXTURE INFORMATION			2/24/2009			4/25/2012			9/19/2012			5/28/2015			9/15/2016			2/20/2019			Summary Status	
Fixture ID	Type	Location	1st Draw	Flush 30s	Pass /Fail	1st Draw	Flush 30s	Pass /Fail	1st Draw	Flush 30s	Pass /Fail	1st Draw	Flush 30s	Pass /Fail	1st Draw	Flush 30s	Pass /Fail	1st Draw	Flush 30s	Pass /Fail	Pass/Fail	Status
02	S/B	area K	0.097	0.07	P	0.085	0.081	P				0.065	0.068	P				0.101	0.1	P	P	None
03	S/B	area K	0.093	0.069	P	0.08	0.08	P				0.053	0.073	P				0.099	0.1	P	P	None
04	S/B	area K	0.083	0.056	P	0.102	0.06	P				0.057	0.055	P				0.109	0.077	P	P	None
05	S/B	area K	0.142	0.099	P	0.114	0.141	P				0.217	0.237	P				0.144	0.131	P	P	None
06	S/B	area B	0.098	0.102	P	0.112	0.106	P				0.078	0.073	P				0.122	0.115	P	P	None
07	S/B	area B	0.085	0.058	P	0.086	0.078	P				0.063	0.063	P				0.1	0.078	P	P	None
07A	S	Area B near #07	0.069	0.055	P	0.072	0.081	P				0.052	0.052	P				0.09	0.066	P	P	None
08	S/B	area A	0.074	0.063	P	0.099	0.077	P				0.062	0.068	P				0.11	0.102	P	P	None
08A	S	Area B near #08	0.115	0.055	P	0.101	0.073	P				0.074	0.062	P				0.122	0.09	P	P	None
09	S/B	area A	0.164	0.127	P	0.134	0.133	P				0.094	0.09	P				0.134	0.107	P	P	None
10	S/B	area D	0.14	0.102	P	0.119	0.112	P				0.112	0.102	P				0.16	0.144	P	P	None
11	S/B	area D (near lav)	0.067	0.05	P	0.078	0.153	P				0.029	0.017	P				0.09	0.156	P	P	None
11A	S	near 11	0.088	0.054	P	0.073	0.153	P				0.051	0.045	P				0.068	0.183	P	P	None
12	S/B	area C (near lav)	0.079	0.071	P	0.086	0.089	P				0.065	0.063	P				0.1	0.098	P	P	None
12A	S	near 12	0.074	0.058	P	0.061	0.05	P				0.053	0.055	P				0.018	0.016	P	P	None
13	S/B	area C	0.229	0.079	P	0.12	0.113	P				0.125	0.12	P				0.148	0.106	P	P	None
14	S/B	off gym	0.098	0.069	P	0.114	0.117	P				0.093	0.084	P							P	None
14A	S	off gym	0.065	0.096	P	0.093	0.084	P				0.067	0.067	P							P	None
14B	S	off gym	0.097	0.062	P	0.108	0.102	P				0.069	0.069	P							P	None
15	S	portable # 4	0.004	0.008	P	0.004	0.004	P				0.006	0.006	P	0.017	0.009	P	0.014	0.016	P	P	None
16	B	womens portable restroom	0.002	<0.002	P	0.002	0.059	P	<0.002	<0.002	P	<0.002	<0.002	P				<0.002	<0.002	P	P	None
17	B	womens portable restroom				0.004	<0.002	P	<0.002	<0.002	P	<0.002	<0.002	P				<0.002	<0.002	P	P	None
18	B	womens portable restroom				<0.002	<0.002	P	<0.002	<0.002	P	<0.002	<0.002	P				<0.002	<0.002	P	P	None
19	B	womens portable restroom				<0.002	<0.002	P	<0.002	<0.002	P	<0.002	<0.002	P				<0.002	<0.002	P	P	None
20	B	mens portable restroom	<0.002	<0.002	P	0.003	0.003	P				<0.002	<0.002	P				<0.002	<0.002	P	P	None
21	B	mens portable restroom				0.003	<0.002	P				<0.002	<0.002	P				<0.002	<0.002	P	P	None
22	B	mens portable restroom	<0.002	<0.002	P	0.002	<0.002	P				<0.002	<0.002	P				<0.002	<0.002	P	P	None
23	B	mens portable restroom	0.003	0.002	P	<0.002	<0.002	P				<0.002	<0.002	P				<0.002	<0.002	P	P	None
25	S	area E	0.236	0.193	P	0.24	0.294	P				0.172	0.207	P				0.216	0.238	P	P	None
26	S	area E	0.273	0.138	P	0.246	0.16	P				0.168	0.146	P				0.231	0.154	P	P	None
27	S	area E	0.155	0.123	P	0.202	0.156	P				0.14	0.133	P				0.188	0.153	P	P	None
31	S	kitchen	0.1	0.051	P	0.134	0.059	P				0.092	0.03	P				0.137	0.058	P	P	None
32	S	area D coffee room	0.19	0.098	P	0.209	0.148	P				0.25	0.1	P				0.465	0.147	P	P	None
33	S	area C work room	0.125	0.065	P	0.202	0.12	P				0.239	0.087	P				0.03	0.026	P	P	None
34	S	commons kitchen	0.234	0.18	P	0.212	0.316	P				0.21	0.24	P				0.305	0.166	P	P	None
35	S	teachers lounge	0.145	0.174	P	0.148	0.156	P				0.1	0.106	P				0.159	0.156	P	P	None
36	S	nurses office	0.167	0.076	P	0.21	0.203	P				0.032	0.038	P				0.214	0.165	P	P	None
37	S	office room sink	0.102	0.054	P	0.093	0.09	P				0.062	0.068	P				0.097	0.078	P	P	None
40	S	Area K north-east corner	0.091	0.054	P	0.094	0.075	P				0.077	0.062	P				0.118	0.107	P	P	None
41	S	Area K workroom	0.166	0.09	P	0.182	0.097	P				0.151	0.166	P				0.188	0.094	P	P	None
42	S	A.B workroom	0.105	0.099	P	0.11	0.111	P				0.085	0.083	P				0.138	0.123	P	P	None
43	S	LMC office (south)	0.131	0.662	P	0.262	0.566	P				0.27	0.387	P				0.438	0.423	P	P	None
44	S	LMC office (north)	0.301	0.238	P	0.099	0.152	P				0.123	0.162	P				0.159	0.309	P	P	None
45	S	Area E (South east)	0.3	0.261	P	0.306	0.4	P				0.345	0.355	P				0.3	0.239	P	P	None
46	S	P7	0.015	0.017	P	0.022	0.01	P				0.046	0.09	P				0.008	0.013	P	P	None
47	S/B	P8	0.038	0.046	P	0.024	0.12	P				0.034	0.042	P				0.015	0.016	P	P	None
48	S	P2	0.005	0.004	P	0.005	0.002	P				0.005	0.003	P							P	None

Table 5. Iron Test Results

Test Results (Iron/Fe, ppm)												
FIXTURE INFORMATION			2/24/2009		4/25/2012		5/28/2015		2/20/2019		Summary Status	
Fixture ID	Type	Location	Flush 2m	Pass/Fail	Flush 2m	Pass/Fail	Flush 2m	Pass/Fail	Flush 2m	Pass/Fail	Pass/Fail	Status
02	S/B	area K			<0.05	P					P	None
03	S/B	area K	<0.05	P							P	None
04	S/B	area K									P	None
05	S/B	area K									P	None
06	S/B	area B									P	None
07	S/B	area B	<0.05	P					<0.05	P	P	None
07A	S	Area B near #07					<0.05	P			P	None
08	S/B	area A			<0.05	P					P	None
08A	S	Area B near #08										
09	S/B	area A									P	None
10	S/B	area D	<0.05	P							P	None
11	S/B	area D (near lav)			<0.05	P					P	None
11A	S	near 11							<0.05	P	P	None
12	S/B	area C (near lav)					<0.05	P			P	None
12A	S	near 12										
13	S/B	area C			<0.05	P					P	None
14	S/B	off gym									P	None
14A	S	off gym										
14B	S	off gym					<0.05	P			P	None
15	S	portable # 4							<0.05	P	P	None
16	B	womens portable restroom									P	None
17	B	womens portable restroom									P	None
18	B	womens portable restroom									P	None
19	B	womens portable restroom									P	None
20	B	mens portable restroom									P	None
21	B	mens portable restroom							<0.05	P	P	None
22	B	mens portable restroom									P	None
23	B	mens portable restroom									P	None
25	S	area E									P	None
26	S	area E									P	None
27	S	area E									P	None
31	S	kitchen							<0.05	P	P	None
32	S	area D coffee room									P	None
33	S	area C work room									P	None
34	S	commons kitchen									P	None
35	S	teachers lounge									P	None
36	S	nurses office	<0.05	P							P	None
37	S	office room sink							<0.05	P	P	None
40	S	Area K north-east corner										
41	S	Area K workroom										
42	S	A.B workroom										
43	S	LMC office (south)										
44	S	LMC office (north)					<0.05	P			P	None
45	S	Area E (South east)	<0.05	P	<0.05	P					P	None
46	S	P7							<0.05	P	P	None
47	S/B	P8										
48	S	P2					<0.05	P			P	None

Table 6. Service Entry Test Results

Test Results (Service Entry/SE, Units as Shown)						
SOURCE INFORMATION			Most Recent Sampling			
Fixture ID	Type	Location	Item	Sampled	Max Value	Pass/Fail
00	SE	custodian's room (mop sink)	Arsenic	28-May-15	2 ppb	P
00	SE	custodian's room (mop sink)	Cadmium	20-Feb-19	1 ppb	P
00	SE	custodian's room (mop sink)	Chlorine	14-Apr-04	0.7 ppm	P
00	SE	custodian's room (mop sink)	Copper	20-Feb-19	0.058 ppm	P
00	SE	custodian's room (mop sink)	E coli	16-Jun-04	<1 Colonies	P
00	SE	custodian's room (mop sink)	Iron	20-Feb-19	<0.05 ppm	P
00	SE	custodian's room (mop sink)	Lead	20-Feb-19	1 ppb	P
00	SE	custodian's room (mop sink)	Total Coliforms	24-Feb-09	<1 Colonies	P

"<" means: less than the value shown (below analytical detection limits).

"n/a" means: not applicable.

Table 7. Bacteriological Test Results

Bacteriological Characteristics

Bacteriological testing of selected samples indicated no (zero) coliform bacteria.