

**Seattle Public Schools
Drinking Water Quality Program**

**Results of Water Quality Testing
for
Concord Elementary**

Updated September 1, 2019

General Information:

Plumbing piping materials: mainly copper

Remediation plan:

This remediation plan is based on a Water Quality policy approved by the School Board. The policy includes standards for the presence of lead, cadmium, copper, iron and other substances in drinking water.

Sinks (S in the report) are not considered drinking water sources. We recognize that there is the potential for students to want to drink from classroom hand-washing sinks, so we test all of those. Where a student's choice to drink from a sink could be a problem, we post a reminder sign, as we do at all restroom sinks.

Status:

All sources meet the policy criteria.

Follow-up monitoring: Will be performed in school year 2021-2022.

Service: The school will be flushed after any breaks longer than five days.

Water Quality Testing Results:

Legend

Symbol	Definition
SE	service entry (main)
B	bubbler
S	sink (faucet)
B/S	sink/bubbler combination
S/B	sink/bubbler combination
ppb	parts per billion
ppm	parts per million
NA	not applicable
None	no action required
Unk	unknown status or action
Sample	sample needs to be taken
Re-test	fixture needs to be resampled
Conf	resample to confirm measurement
No flush	not flushed before sampling
Sink	sampled faucet of S/B combo
Used	recently used; no 1st draw sample possible
PS	post sign
Disable(d)	fixture disabled in response to water quality testing
BDSS	Bubbler disabled, sign on sink
IF	install filter
RB	replace bubbler
RB/IF	replace bubbler and/or install filter
RF	replace faucet
RF/IF	replace faucet and/or install filter
BW	disable fixture and provide bottled water until remediated
Leaks	leaking fixture
NW	not working properly (sample S when B of S/B NW)
OS	out of service - disabled until fixed
RS	return to service - now passes testing
Rem	Removed from system - no longer exists

Table 1. Summary of Results

FIXTURE INFORMATION			CURRENT STATUS								
Fixture ID	Type	Location	LEAD		CADMIUM		COPPER		IRON		OK?
			Pass/Fail	Status	Pass/Fail	Status	Pass/Fail	Status	Pass/Fail	Status	Yes/No/Status
01	B	off main foyer, W lefthand	P	None	P	None	P	None	P	None	Yes
02	B	off main foyer, E righthand	P	None	P	None	P	None			Yes
03	S/B	room 101	P	None	P	None	P	None			Yes
04	S/B	room 103	P	None	P	None	P	None			Yes
05	S/B	room 105	P	None	P	None	P	None			Yes
06	S/B	room 107	P	None	P	None	P	None			Yes
07	S/B	room 109	P	None	P	None	P	None	P	None	Yes
09	S/B	room 108	P	None	P	None	P	None	P	None	Yes
10	S/B	room 106	P	None	P	None	P	None	P	None	Yes
11	S/B	room 209	P	None	P	None	P	None	P	None	Yes
12	S/B	room 210	P	None	P	None	P	None	P	None	Yes
13	S/B	room 207	P	None	P	None	P	None	P	None	Yes
14	S/B	room 208	P	None	P	None	P	None	P	None	Yes
15	S/B	room 205	P	None	P	None	P	None			Yes
16	S/B	room 206	P	None	P	None	P	None			Yes
17	S/B	room 203	P	None	P	None	P	None			Yes
18	S/B	room 201	P	None	P	None	P	None			Yes
19	B	2nd floor off foyer (w), left	P	None	P	None	P	None			Yes
20	B	2nd floor off foyer (e), right	P	None	P	None	P	None			Yes
21	S/B	room 221	P	None	P	None	P	None			Yes
22	S/B	room 233	P	None	P	None	P	None	P	None	Yes
23	S/B	room 230	P	None	P	None	P	None			Yes
24	S/B	room 222	P	None	P	None	P	None			Yes
25	B	2nd floor, east stair case (w), left	P	None	P	None	P	None			Yes
26	B	2nd floor, east stair case (e), right	P	None	P	None	P	None	P	None	Yes
27	B	3rd floor, west stair case (w), left	P	None	P	None	P	None			Yes
28	B	3rd floor, west stair case (e), right	P	None	P	None	P	None			Yes
29	S	lounge	P	None	P	None	P	None	P	None	Yes
30	B	3rd floor, east stair case (w), left	P	None	P	None	P	None	P	None	Yes
31	B	3rd floor, east stair case (e),right	P	None	P	None	P	None	P	None	Yes
37	S	nurses office	P	None	P	None	P	None	P	None	Yes
38	B	1st floor, s. stair case (w), left	P	None	P	None	P	None	P	None	Yes
39	B	1st floor, s. stair case (e), right	P	None	P	None	P	None	P	None	Yes
40	B	east foyer (n), left	P	None	P	None	P	None	P	None	Yes
41	B	east foyer (s), right	P	None	P	None	P	None	P	None	Yes
42	S	kitchen (east wall) - left hand west	P	None	P	None	P	None	P	None	Yes
43	B	trash room (s), left	P	None	P	None	P	None	P	None	Yes
44	B	trash room (n), right	P	None	P	None	P	None			Yes
49	S	room 320 - LCR	P	None	P	None	P	None			Yes
50	S	Kitchen entry lobby by freezer	P	None	P	None	P	None			Yes
51	S	Kitchen east wall, right hand east; sister of 42	P	None	P	None	P	None			Yes
52	S	office work room	P	None	P	None	P	None			Yes
54	S	room 110	P	None	P	None	P	None	P	None	Yes
55	S	room 121i	P	None	P	None	P	None			Yes
56	BF	east foyer, bottle filler	P	None	P	None	P	None			Yes

Table 2. Lead Test Results

FIXTURE INFORMATION			7/31/2009			10/7/2009			9/25/2012			10/8/2015			7/19/2019			Summary Status	
Fixture ID	Type	Location	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	Pass/Fail	Status
01	B	off main foyer, W lefthand	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
02	B	off main foyer, E righthand	1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
03	S/B	room 101	3	1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
04	S/B	room 103	12	2		3	<1	P	2	<1	P	<1	<1	P	<1	<1	P	P	None
05	S/B	room 105	5	2	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
06	S/B	room 107	2	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
07	S/B	room 109	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
09	S/B	room 108	1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
10	S/B	room 106	5	1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
11	S/B	room 209	1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
12	S/B	room 210	1	<1	P				2	<1	P	1	<1	P	<1	<1	P	P	None
13	S/B	room 207	2	<1	P				1	<1	P	<1	<1	P	<1	<1	P	P	None
14	S/B	room 208	3	<1	P				3	1	P	1	<1	P	<1	<1	P	P	None
15	S/B	room 205	1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
16	S/B	room 206	1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
17	S/B	room 203	2	<1	P				2	<1	P	<1	<1	P	<1	<1	P	P	None
18	S/B	room 201	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
19	B	2nd floor off foyer (w), left	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
20	B	2nd floor off foyer (e), right	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
21	S/B	room 221	<1	<1	P				1	<1	P	<1	<1	P	<1	<1	P	P	None
22	S/B	room 233	2	<1	P				<1	<1	P	1	<1	P	<1	<1	P	P	None
23	S/B	room 230	4	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
24	S/B	room 222	1	<1	P				1	<1	P	<1	<1	P	<1	<1	P	P	None
25	B	2nd floor, east stair case (w), left	2	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
26	B	2nd floor, east stair case (e), right	1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
27	B	3rd floor, west stair case (w), left	<1	<1	P				2	<1	P	2	<1	P	<1	<1	P	P	None
28	B	3rd floor, west stair case (e), right	6	3	P				<1	<1	P	<1	<1	P	<1	4	P	P	None
29	S	lounge	1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
30	B	3rd floor, east stair case (w), left	1	<1	P				<1	<1	P				1	<1	P	P	None
31	B	3rd floor, east stair case (e),right	1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
37	S	nurses office	2	1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
38	B	1st floor, s. stair case (w), left	1	1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
39	B	1st floor, s. stair case (e), right	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
40	B	east foyer (n), left	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
41	B	east foyer (s), right	1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
42	S	kitchen (east wall) - left hand west	5	<1	P				<1	<1	P	3	<1	P	<1	<1	P	P	None
43	B	trash room (s), left	1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
44	B	trash room (n), right	1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
49	S	room 320 - LCR	5	<1	P				1	<1	P	<1	<1	P	<1	<1	P	P	None
50	S	Kitchen entry lobby by freezer	54	1		1	<1	P	2	<1	P	3	<1	P	3	<1	P	P	None
51	S	Kitchen east wall, right hand east; sister of 42	3	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
52	S	office work room	<1	<1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
54	S	room 110	2	<1	P				1	<1	P	<1	<1	P	<1	<1	P	P	None
55	S	room 121i	<1	1	P				<1	<1	P	<1	<1	P	<1	<1	P	P	None
56	BF	east foyer, bottle filler													<1	<1	P	P	None

Table 3. Cadmium Test Results

FIXTURE INFORMATION			7/31/2009			9/25/2012			10/8/2015			7/19/2019			Summary Status	
Fixture ID	Type	Location	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	Pass/Fail	Status
01	B	off main foyer, W lefthand	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
02	B	off main foyer, E righthand	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
03	S/B	room 101	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
04	S/B	room 103	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
05	S/B	room 105	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
06	S/B	room 107	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
07	S/B	room 109	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
09	S/B	room 108	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
10	S/B	room 106	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
11	S/B	room 209	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
12	S/B	room 210	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
13	S/B	room 207	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
14	S/B	room 208	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
15	S/B	room 205	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
16	S/B	room 206	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
17	S/B	room 203	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
18	S/B	room 201	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
19	B	2nd floor off foyer (w), left	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
20	B	2nd floor off foyer (e), right	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
21	S/B	room 221	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
22	S/B	room 233	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
23	S/B	room 230	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
24	S/B	room 222	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
25	B	2nd floor, east stair case (w), left	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
26	B	2nd floor, east stair case (e), right	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
27	B	3rd floor, west stair case (w), left	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
28	B	3rd floor, west stair case (e), right	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
29	S	lounge	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
30	B	3rd floor, east stair case (w), left	<1	<1	P	<1	<1	P				<1	<1	P	P	None
31	B	3rd floor, east stair case (e),right	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
37	S	nurses office	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
38	B	1st floor, s. stair case (w), left	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
39	B	1st floor, s. stair case (e), right	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
40	B	east foyer (n), left	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
41	B	east foyer (s), right	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
42	S	kitchen (east wall) - left hand west	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
43	B	trash room (s), left	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
44	B	trash room (n), right	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
49	S	room 320 - LCR	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
50	S	Kitchen entry lobby by freezer	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
51	S	Kitchen east wall, right hand east; sister of 42	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
52	S	office work room	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
54	S	room 110	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
55	S	room 121i	<1	<1	P	<1	<1	P	<1	<1	P	<1	<1	P	P	None
56	BF	east foyer, bottle filler										<1	<1	P	P	None

Table 4. Copper Test Results

FIXTURE INFORMATION			7/31/2009			9/25/2012			10/8/2015			7/19/2019			Summary Status	
Fixture ID	Type	Location	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	1st Draw	Flush 30s	Pass/Fail	Pass/Fail	Status
01	B	off main foyer, W lefthand	0.406	0.237	P	0.213	0.138	P	0.126	0.088	P	0.135	0.111	P	P	None
02	B	off main foyer, E righthand	0.377	0.202	P	0.2	0.146	P	0.121	0.058	P	0.134	0.082	P	P	None
03	S/B	room 101	0.33	0.207	P	0.19	0.186	P	0.119	0.06	P	0.128	0.087	P	P	None
04	S/B	room 103	0.33	0.383	P	0.18	0.232	P	0.125	0.069	P	0.155	0.073	P	P	None
05	S/B	room 105	0.294	0.395	P	0.264	0.221	P	0.144	0.09	P	0.168	0.09	P	P	None
06	S/B	room 107	0.347	0.306	P	0.217	0.262	P	0.134	0.097	P	0.177	0.119	P	P	None
07	S/B	room 109	0.408	0.523	P	0.239	0.213	P	0.139	0.132	P	0.211	0.136	P	P	None
09	S/B	room 108	0.358	0.31	P	0.221	0.256	P	0.131	0.099	P	0.149	0.102	P	P	None
10	S/B	room 106	0.468	0.343	P	0.196	0.231	P	0.122	0.083	P	0.167	0.096	P	P	None
11	S/B	room 209	0.382	0.387	P	0.227	0.224	P	0.12	0.122	P	0.558	0.177	P	P	None
12	S/B	room 210	0.382	0.512	P	0.293	0.199	P	0.196	0.126	P	0.573	0.145	P	P	None
13	S/B	room 207	0.369	0.394	P	0.201	0.216	P	0.123	0.13	P	0.227	0.099	P	P	None
14	S/B	room 208	0.414	0.398	P	0.228	0.217	P	0.112	0.109	P	0.136	0.095	P	P	None
15	S/B	room 205	0.368	0.335	P	0.209	0.196	P	0.128	0.128	P	0.112	0.087	P	P	None
16	S/B	room 206	0.404	0.48	P	0.225	0.21	P	0.131	0.116	P	0.1	0.08	P	P	None
17	S/B	room 203	0.338	0.284	P	0.211	0.206	P	0.109	0.111	P	0.163	0.1	P	P	None
18	S/B	room 201	0.355	0.37	P	0.194	0.172	P	0.108	0.075	P	0.082	0.061	P	P	None
19	B	2nd floor off foyer (w), left	0.501	0.369	P	0.14	0.137	P	0.035	0.032	P	0.285	0.137	P	P	None
20	B	2nd floor off foyer (e), right	0.201	0.201	P	0.253	0.251	P	0.142	0.1	P	0.069	0.051	P	P	None
21	S/B	room 221	0.406	0.177	P	0.188	0.142	P	0.113	0.084	P	0.147	0.096	P	P	None
22	S/B	room 233	0.285	0.16	P	0.16	0.065	P	0.084	0.042	P	0.143	0.063	P	P	None
23	S/B	room 230	0.302	0.392	P	0.256	0.262	P	0.118	0.124	P	0.143	0.157	P	P	None
24	S/B	room 222	0.377	0.242	P	0.199	0.223	P	0.106	0.115	P	0.145	0.155	P	P	None
25	B	2nd floor, east stair case (w), left	0.372	0.154	P	0.291	0.271	P	0.266	0.246	P	0.106	0.082	P	P	None
26	B	2nd floor, east stair case (e), right	0.534	0.192	P	0.198	0.108	P	0.071	0.034	P	0.335	0.207	P	P	None
27	B	3rd floor, west stair case (w), left	0.447	0.462	P	0.138	0.13	P	0.046	0.029	P	0.291	0.266	P	P	None
28	B	3rd floor, west stair case (e), right	0.38	0.337	P	0.309	0.281	P	0.182	0.152	P	0.115	0.092	P	P	None
29	S	lounge	0.308	0.247	P	0.148	0.138	P	0.067	0.054	P	0.119	0.121	P	P	None
30	B	3rd floor, east stair case (w), left	0.448	0.374	P	0.289	0.253	P				0.264	0.18	P	P	None
31	B	3rd floor, east stair case (e),right	0.616	0.572	P	0.253	0.146	P	0.148	0.105	P	0.342	0.328	P	P	None
37	S	nurses office	0.315	0.289	P	0.171	0.173	P	0.101	0.104	P	0.152	0.123	P	P	None
38	B	1st floor, s. stair case (w), left	0.313	0.158	P	0.183	0.163	P	0.03	0.027	P	0.153	0.071	P	P	None
39	B	1st floor, s. stair case (e), right	0.433	0.189	P	0.2	0.106	P	0.1	0.047	P	0.153	0.084	P	P	None
40	B	east foyer (n), left	0.359	0.348	P	0.168	0.16	P	0.093	0.075	P	0.093	0.081	P	P	None
41	B	east foyer (s), right	0.33	0.252	P	0.171	0.159	P	0.085	0.071	P	0.077	0.083	P	P	None
42	S	kitchen (east wall) - left hand west	0.316	0.088	P	0.047	0.034	P	0.062	0.032	P	0.094	0.071	P	P	None
43	B	trash room (s), left	0.424	0.128	P	0.243	0.047	P	0.171	0.087	P	0.164	0.092	P	P	None
44	B	trash room (n), right	0.513	0.087	P	0.224	0.035	P	0.129	0.048	P	0.182	0.116	P	P	None
49	S	room 320 - LCR	0.31	0.452	P	0.27	0.303	P	0.174	0.182	P	0.245	0.285	P	P	None
50	S	Kitchen entry lobby by freezer	1.26	0.087	P	0.215	0.033	P	0.14	0.083	P	0.217	0.154	P	P	None
51	S	Kitchen east wall, right hand east; sister of 42	0.348	0.067	P	0.053	0.037	P	0.031	0.029	P	0.082	0.076	P	P	None
52	S	office work room	0.29	0.152	P	0.157	0.14	P	0.08	0.058	P	0.124	0.053	P	P	None
54	S	room 110	0.374	0.432	P	0.213	0.231	P	0.083	0.075	P	0.186	0.125	P	P	None
55	S	room 121i	0.138	0.262	P	0.135	0.147	P	0.097	0.123	P	0.142	0.16	P	P	None
56	BF	east foyer, bottle filler										0.091	0.083	P	P	None

Table 5. Iron Test Results

FIXTURE INFORMATION			7/31/2009		9/25/2012		10/8/2015		7/19/2019		Summary Status	
Fixture ID	Type	Location	Flush 2m	Pass/Fail	Flush 2m	Pass/Fail	Flush 2m	Pass/Fail	Flush 2m	Pass/Fail	Pass/Fail	Status
01	B	off main foyer, W lefthand									P	None
02	B	off main foyer, E righthand										
03	S/B	room 101										
04	S/B	room 103										
05	S/B	room 105										
06	S/B	room 107										
07	S/B	room 109	<0.05	P							P	None
09	S/B	room 108			<0.05	P					P	None
10	S/B	room 106					<0.05	P			P	None
11	S/B	room 209	<0.05	P					<0.05	P	P	None
12	S/B	room 210			<0.05	P					P	None
13	S/B	room 207					<0.05	P			P	None
14	S/B	room 208							<0.05	P	P	None
15	S/B	room 205										
16	S/B	room 206										
17	S/B	room 203										
18	S/B	room 201										
19	B	2nd floor off foyer (w), left										
20	B	2nd floor off foyer (e), right										
21	S/B	room 221										
22	S/B	room 233	<0.05	P							P	None
23	S/B	room 230										
24	S/B	room 222										
25	B	2nd floor, east stair case (w), left										
26	B	2nd floor, east stair case (e), right							<0.05	P	P	None
27	B	3rd floor, west stair case (w), left										
28	B	3rd floor, west stair case (e), right										
29	S	lounge	<0.05	P							P	None
30	B	3rd floor, east stair case (w), left			<0.05	P					P	None
31	B	3rd floor, east stair case (e),right	<0.05	P			<0.05	P			P	None
37	S	nurses office							<0.05	P	P	None
38	B	1st floor, s. stair case (w), left			<0.05	P					P	None
39	B	1st floor, s. stair case (e), right	<0.05	P			<0.05	P			P	None
40	B	east foyer (n), left									P	None
41	B	east foyer (s), right			<0.05	P					P	None
42	S	kitchen (east wall) - left hand west					<0.05	P			P	None
43	B	trash room (s), left							<0.05	P	P	None
44	B	trash room (n), right										
49	S	room 320 - LCR										
50	S	Kitchen entry lobby by freezer										
51	S	Kitchen east wall, right hand east; sister of 42										
52	S	office work room										
54	S	room 110							<0.05	P	P	None
55	S	room 121i										
56	BF	east foyer, bottle filler										

Table 6. Service Entry Test Results

Test Results (Service Entry/SE, Units as Shown)						
SOURCE INFORMATION			Most Recent Sampling			
Fixture ID	Type	Location	Item	Sampled	Max Value	Pass/Fail
00	SE	Cafeteria storage fire sprinkler valve room	Arsenic	08-Oct-15	2 ppb	P
00	SE	Cafeteria storage fire sprinkler valve room	Cadmium	08-Oct-15	1 ppb	P
00	SE	Cafeteria storage fire sprinkler valve room	Copper	08-Oct-15	0.04 ppm	P
00	SE	Cafeteria storage fire sprinkler valve room	E coli	04-Aug-04	<1 Colonies	P
00	SE	Cafeteria storage fire sprinkler valve room	Iron	08-Oct-15	<0.05 ppm	P
00	SE	Cafeteria storage fire sprinkler valve room	Lead	08-Oct-15	1 ppb	P
00	SE	Cafeteria storage fire sprinkler valve room	Total Coliforms	04-Aug-04	<1 Colonies	P

"<" means: less than the value shown (below analytical detection limits).

"n/a" means: not applicable.

Table 7. Bacteriological Test Results

Bacteriological Characteristics

Bacteriological testing of selected samples indicated no (zero) coliform bacteria.